

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT				
APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER Lusty 1-11-3-3W				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT WILDCAT				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY						7. OPERATOR PHONE 435 646-4825				
8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052						9. OPERATOR E-MAIL mcrozier@newfield.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) patented			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee') David A. Evans & Alicia L. Evans						14. SURFACE OWNER PHONE (if box 12 = 'fee') 435-823-3432				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') HC 64 Box 390, Duchesne, UT 84021						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN		
LOCATION AT SURFACE		60 FNL 1121 FEL		NENE		3.0 S	3.0 W	U		
Top of Uppermost Producing Zone		60 FNL 1121 FEL		NENE	11	3.0 S	3.0 W	U		
At Total Depth		660 FNL 1109 FEL		NENE	11	3.0 S	3.0 W	U		
21. COUNTY DUCESNE			22. DISTANCE TO NEAREST LEASE LINE (Feet) 60			23. NUMBER OF ACRES IN DRILLING UNIT 40				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Approved For Drilling or Completed) 1495			26. PROPOSED DEPTH MD: 11030 TVD: 11000				
27. ELEVATION - GROUND LEVEL 5307			28. BOND NUMBER B001834			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
COND	17.5	14	0 - 60	37.0	H-40 ST&C	0.0	Class G	35	1.17	15.8
SURF	12.25	9.625	0 - 1000	36.0	J-55 LT&C	8.3	Premium Lite High Strength	51	3.53	11.0
							Class G	154	1.17	15.8
I1	8.75	7	0 - 8688	26.0	P-110 LT&C	9.5	Premium Lite High Strength	284	3.53	11.0
							50/50 Poz	262	1.24	14.3
PROD	6.125	4.5	8488 - 11030	11.6	P-110 LT&C	11.5	50/50 Poz	222	1.24	14.3
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Don Hamilton				TITLE Permitting Agent			PHONE 435 719-2018			
SIGNATURE				DATE 05/15/2012			EMAIL starpoint@etv.net			
API NUMBER ASSIGNED 43013514120000				APPROVAL Permit Manager						

Newfield Production Company
Lusty 1-11-3-3W
NE/NE Section 11, T3S, R3W
Duchesne County, UT

Drilling Program

1. Formation Tops	TVD	MD
Uinta	surface	surface
Green River	3,892'	3,892'
Garden Gulch member	6,807'	6,834'
Wasatch	9,286'	9,319'
TD	11,000'	11,030'

2. Depth to Oil, Gas, Water, or Minerals	TVD	
Base of moderately saline	681'	(water)
Green River	6,807' - 9,286'	(oil)
Wasatch	9,286' - TD	(oil)

3. Pressure Control

Section BOP Description

Surface 12-1/4" diverter

Interm/Prod The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc for a 5M system.

A 5M BOP system will consist of 2 ram preventers (double or two singles) and an annular preventer (see attached diagram). A choke manifold rated to at least 5,000 psi will be used.

4. Casing

Description	Interval (MD)		Weight (ppf)	Grade	Coupl	Pore Press @ Shoe	MW @ Shoe	Frac Grad @ Shoe	Safety Factors		
	Top	Bottom							Burst	Collapse	Tension
Conductor	0'	60'	37	H-40	Weld	--	--	--	--	--	--
14									--	--	--
Surface	0'	1,000'	36	J-55	LTC	8.33	8.33	12	3,520	2,020	453,000
9 5/8									6.27	6.35	12.58
Intermediate	0'	8,688'	26	P-110	LTC	9	9.5	15	9,960	6,210	693,000
7									2.43	1.81	3.07
Production	8,488'	11,030'	11.6	P-110	LTC	11	11.5	--	10,690	7,560	279,000
4 1/2									2.05	1.38	2.18

Assumptions:

Surface casing MASP = (frac gradient + 1.0 ppg) - (gas gradient)

Intermediate casing MASP = (reservoir pressure) - (gas gradient)

Production casing MASP = (reservoir pressure) - (gas gradient)

All collapse calculations assume fully evacuated casing with a gas gradient

All tension calculations assume air weight of casing

Gas gradient = 0.1 psi/ft

All casing shall be new.

All casing strings shall have a minimum of 1 centralizer on each of the bottom 3 joints.

5. Cement

Job	Hole Size	Fill	Slurry Description	ft ³	OH excess	Weight (ppg)	Yield (ft ³ /sk)
				sacks			
Conductor	17 1/2	60'	Class G w/ 2% KCl + 0.25 lbs/sk Cello Flake	41	15%	15.8	1.17
				35			
Surface Lead	12 1/4	500'	Premium Lite II w/ 3% KCl + 10% bentonite	180	15%	11.0	3.53
				51			
Surface Tail	12 1/4	500'	Class G w/ 2% KCl + 0.25 lbs/sk Cello Flake	150	15%	15.8	1.17
				154			
Intermediate Lead	8 3/4	5,807'	Premium Lite II w/ 3% KCl + 10% bentonite	1004	15%	11.0	3.53
				284			
Intermediate Tail	8 3/4	1,881'	50/50 Poz/Class G w/ 3% KCl + 2% bentonite	325	15%	14.3	1.24
				262			
Production Tail	6 1/8	2,542'	50/50 Poz/Class G w/ 3% KCl + 2% bentonite	275	15%	14.3	1.24
				222			

The surface casing will be cemented to surface. In the event that cement does not reach surface during the primary cement job, a remedial job will be performed.

Actual cement volumes for the intermediate and production casing strings will be calculated from an open hole caliper log, plus 15% excess.

6. Type and Characteristics of Proposed Circulating Medium

<u>Interval</u>	<u>Description</u>
Surface - 1,000'	An air and/or fresh water system will be utilized. If an air rig is used, the blooie line discharge may be less than 100' from the wellbore in order to minimize location size. The blooie line is not equipped with an automatic igniter. The air compressor may be located less than 100' from the well bore due to the low possibility of combustion with the air/dust mixture. Water will be on location to be used as kill fluid, if necessary.
1,000' - TD	A water based mud system will be utilized. Hole stability may be improved with additions of KCl or a similar inhibitive substance. In order to control formation pressure the system will be weighted with additions of bentonite, and if conditions warrant, with barite.

Anticipated maximum mud weight is 11.5 ppg.

7. Logging, Coring, and Testing

Logging: A dual induction, gamma ray, and caliper log will be run from TD to the base of the surface casing. A compensated neutron/formation density log will be run from TD to the top of the Garden Gulch formation. A cement bond log will be run from PBTD to the cement top behind the production casing.

Cores: As deemed necessary.

DST: There are no DST's planned for this well.

8. Anticipated Abnormal Pressure or Temperature

Maximum anticipated bottomhole pressure will be approximately equal to total depth (feet) multiplied by a 0.57 psi/ft gradient.

$$11,000' \times 0.57 \text{ psi/ft} = 6292 \text{ psi}$$

No abnormal temperature is expected. No H₂S is expected.


9. Other Aspects

This is planned as a "S" shaped directional well. See attached directional plan.

Newfield requests the following variances from Onshore Order #2:

- Variance from Onshore Order #2, III.E.1

Refer to Newfield Production Company Standard Operating Practices "Ute Tribal Green River Development Program" paragraph 9.0

T3S, R3W, U.S.B.&M.**NEWFIELD EXPLORATION COMPANY**


◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; Elevations are based on an N.G.S. OPUS Correction. LOCATION: LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'

1-11-3-3W
(Surface Location) NAD 83
 LATITUDE = 40° 14' 36.89"
 LONGITUDE = 110° 11' 04.75"


WELL LOCATION, 1-11-3-3W, LOCATED AS SHOWN IN THE NE 1/4 NE 1/4 OF SECTION 11, T3S, R3W, U.S.B.&M. DUCHESNE COUNTY, UTAH.

TARGET BOTTOM HOLE, 1-11-3-3W, LOCATED AS SHOWN IN THE NE 1/4 NE 1/4 OF SECTION 11, T3S, R3W, U.S.B.&M. DUCHESNE COUNTY, UTAH.

**NOTES:**

1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.
3. The Bottom of Hole bears S02°10'48"E 599.97' from the Top of Hole.

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.


**TRI STATE LAND SURVEYING & CONSULTING**

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
 (435) 781-2501

DATE SURVEYED: 04-17-12	SURVEYED BY: S.H.	VERSION:
DATE DRAWN: 12-14-11	DRAWN BY: R.B.T.	V9
REVISED: 05-11-12 R.B.T.	SCALE: 1" = 1000'	

RECEIVED: May 15, 2012

Access Road Map



Legend

- Existing Road
 Proposed Road



**Tri State
Land Surveying, Inc.**

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518

**NEWFIELD EXPLORATION COMPANY**

2-11-3-WH
 1-11-3-W
 SEC. 11, T3S, R3W, U.S.B.&M.
 Duchesne County, UT.


DRAWN BY:	A.P.C.	REVISED:	05-11-12 D.C.R.	VERSION:
DATE:	12-14-11			V9
SCALE:	1:100,000			

TOPOGRAPHIC MAP

SHEET

A

Access Road Map



Legend

- Existing Road
- Proposed Road
- Culvert Required
- Cattle Guard Required

Total Road Distances

Proposed Road ± 8,233'

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY


2-11-3-3WH
1-11-3-3W
SEC. 11, T3S, R3W, U.S.B.&M.
Duchesne County, UT.

DRAWN BY:	A.P.C.	REVISED:	05-11-12 D.C.R.	VERSION:
DATE:	12-14-2011			V9
SCALE:	1" = 2,000'			

TOPOGRAPHIC MAP

SHEET
B

Proposed Pipeline Map



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

2-11-3-3WH
1-11-3-3W
SEC. 11, T3S, R3W, U.S.B.&M.
Duchesne County, UT.

DRAWN BY:	A.P.C.	REVISED:	05-11-12 D.C.R.	VERSION:
DATE:	12-14-2011			V9
SCALE:	1" = 2,000'			

TOPOGRAPHIC MAP

SHEET

C

Exhibit "B" Map

2-11-3-3WH
1-11-3-3W

CONFIDENTIAL

Legend

- 1 Mile Radius
● Proposed Location

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

2-11-3-3WH
1-11-3-3W
SEC. 11, T3S, R3W, U.S.B.&M.
Duchesne County, UT.

DRAWN BY:	A.P.C.	REVISED:	05-11-12 D.C.R.	VERSION:
DATE:	12-14-2011			V9
SCALE:	1" = 2,000'			

TOPOGRAPHIC MAP

SHEET



D



Newfield Production Company

Project: Uinta Basin
Site: Lusty 1-11-3-3W
Well: Lusty 1-11-3-3W
Wellbore: Wellbore #1
Design: Design #1

M Azimuths to True North
 Magnetic North: 11.26°
 Magnetic Field
 Strength: 52316.6snT
 Dip Angle: 65.92°
 Date: 5/5/2012
 Model: IGRF200510



PROJECT DETAILS: Uinta Basin

Geodetic System: US State Plane 1983
Datum: North American Datum 1983
Ellipsoid: GRS 1980
Zone: Utah Central Zone

System Datum: Mean Sea Level

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	Vsect	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	1100.0	0.00	0.00	1100.0	0.0	0.0	0.00	0.00	0.0	
3	1293.3	5.80	177.82	1293.0	-9.8	0.4	3.00	177.82	9.8	
4	7036.7	5.80	177.82	7007.0	-589.8	22.5	0.00	0.00	590.2	
5	7230.1	0.00	0.00	7200.0	-599.5	22.8	3.00	180.00	600.0	
6	1030.1	0.00	0.00	11000.0	-599.5	22.8	0.00	0.00	600.0	1-11-3-3W BHL

Newfield Production Company

Uinta Basin

Lusty 1-11-3-3W

Lusty 1-11-3-3W

Wellbore #1

Plan: Design #1

Standard Planning Report

14 May 2012

CONFIDENTIAL

Newfield Exploration

Planning Report

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Lusty 1-11-3-3W
Company:	Newfield Production Company	TVD Reference:	RKB @ 5326.0ft
Project:	Uinta Basin	MD Reference:	RKB @ 5326.0ft
Site:	Lusty 1-11-3-3W	North Reference:	True
Well:	Lusty 1-11-3-3W	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Project	Uinta Basin		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Central Zone		

Site		Lusty 1-11-3-3W			
Site Position:		Northing:	2,212,907.54 m	Latitude:	40° 14' 37.190 N
From:	Lat/Long	Easting:	611,909.80 m	Longitude:	110° 11' 4.750 W
Position Uncertainty:	0.0 ft	Slot Radius:	0.000 in	Grid Convergence:	0.84 °

Well	Lusty 1-11-3-3W					
Well Position	+N-S	0.0 ft	Northing:	2,212,907.54 m	Latitude:	40° 14' 37.190 N
	+E-W	0.0 ft	Easting:	611,909.80 m	Longitude:	110° 11' 4.750 W
Position Uncertainty		0.0 ft	Wellhead Elevation:		Ground Level:	5,308.0 ft

Wellbore	Wellbore #1				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF200510	5/5/2012	11.26	65.92	52,317

Design	Design #1			
Audit Notes:				
Version:	Phase:	PROTOTYPE	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (ft)	+N-S (ft)	+E-W (ft)	Direction (°)
	0.0	0.0	0.0	177.82

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N-S (ft)	+E-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,293.3	5.80	177.82	1,293.0	-9.8	0.4	3.00	3.00	0.00	177.82	
7,036.7	5.80	177.82	7,007.0	-589.8	22.5	0.00	0.00	0.00	0.00	
7,230.1	0.00	0.00	7,200.0	-599.5	22.8	3.00	-3.00	0.00	180.00	
11,030.1	0.00	0.00	11,000.0	-599.5	22.8	0.00	0.00	0.00	0.00	1-11-3-3W BHL

Newfield Exploration

Planning Report

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Lusty 1-11-3-3W
Company:	Newfield Production Company	TVD Reference:	RKB @ 5326.0ft
Project:	Uinta Basin	MD Reference:	RKB @ 5326.0ft
Site:	Lusty 1-11-3-3W	North Reference:	True
Well:	Lusty 1-11-3-3W	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00
1,200.0	3.00	177.82	1,200.0	-2.6	0.1	2.6	3.00	3.00	0.00
1,293.3	5.80	177.82	1,293.0	-9.8	0.4	9.8	3.00	3.00	0.00
1,300.0	5.80	177.82	1,299.6	-10.4	0.4	10.5	0.00	0.00	0.00
1,400.0	5.80	177.82	1,399.1	-20.5	0.8	20.6	0.00	0.00	0.00
1,500.0	5.80	177.82	1,498.6	-30.6	1.2	30.7	0.00	0.00	0.00
1,600.0	5.80	177.82	1,598.1	-40.7	1.6	40.8	0.00	0.00	0.00
1,700.0	5.80	177.82	1,697.6	-50.8	1.9	50.9	0.00	0.00	0.00
1,800.0	5.80	177.82	1,797.1	-60.9	2.3	61.0	0.00	0.00	0.00
1,900.0	5.80	177.82	1,896.6	-71.0	2.7	71.1	0.00	0.00	0.00
2,000.0	5.80	177.82	1,996.1	-81.1	3.1	81.2	0.00	0.00	0.00
2,100.0	5.80	177.82	2,095.5	-91.2	3.5	91.3	0.00	0.00	0.00
2,200.0	5.80	177.82	2,195.0	-101.3	3.9	101.4	0.00	0.00	0.00
2,300.0	5.80	177.82	2,294.5	-111.4	4.2	111.5	0.00	0.00	0.00
2,400.0	5.80	177.82	2,394.0	-121.5	4.6	121.6	0.00	0.00	0.00
2,500.0	5.80	177.82	2,493.5	-131.6	5.0	131.7	0.00	0.00	0.00
2,600.0	5.80	177.82	2,593.0	-141.7	5.4	141.8	0.00	0.00	0.00
2,700.0	5.80	177.82	2,692.5	-151.8	5.8	151.9	0.00	0.00	0.00
2,800.0	5.80	177.82	2,792.0	-161.9	6.2	162.0	0.00	0.00	0.00
2,900.0	5.80	177.82	2,891.4	-172.0	6.5	172.1	0.00	0.00	0.00
3,000.0	5.80	177.82	2,990.9	-182.1	6.9	182.2	0.00	0.00	0.00
3,100.0	5.80	177.82	3,090.4	-192.2	7.3	192.4	0.00	0.00	0.00
3,200.0	5.80	177.82	3,189.9	-202.3	7.7	202.5	0.00	0.00	0.00
3,300.0	5.80	177.82	3,289.4	-212.4	8.1	212.6	0.00	0.00	0.00
3,400.0	5.80	177.82	3,388.9	-222.5	8.5	222.7	0.00	0.00	0.00
3,500.0	5.80	177.82	3,488.4	-232.6	8.9	232.8	0.00	0.00	0.00
3,600.0	5.80	177.82	3,587.9	-242.7	9.2	242.9	0.00	0.00	0.00
3,700.0	5.80	177.82	3,687.3	-252.8	9.6	253.0	0.00	0.00	0.00
3,800.0	5.80	177.82	3,786.8	-262.9	10.0	263.1	0.00	0.00	0.00
3,900.0	5.80	177.82	3,886.3	-273.0	10.4	273.2	0.00	0.00	0.00
4,000.0	5.80	177.82	3,985.8	-283.1	10.8	283.3	0.00	0.00	0.00
4,100.0	5.80	177.82	4,085.3	-293.2	11.2	293.4	0.00	0.00	0.00
4,200.0	5.80	177.82	4,184.8	-303.3	11.5	303.5	0.00	0.00	0.00
4,300.0	5.80	177.82	4,284.3	-313.4	11.9	313.6	0.00	0.00	0.00
4,400.0	5.80	177.82	4,383.8	-323.5	12.3	323.7	0.00	0.00	0.00
4,500.0	5.80	177.82	4,483.3	-333.6	12.7	333.8	0.00	0.00	0.00
4,600.0	5.80	177.82	4,582.7	-343.7	13.1	343.9	0.00	0.00	0.00
4,700.0	5.80	177.82	4,682.2	-353.8	13.5	354.0	0.00	0.00	0.00
4,800.0	5.80	177.82	4,781.7	-363.9	13.9	364.2	0.00	0.00	0.00
4,900.0	5.80	177.82	4,881.2	-374.0	14.2	374.3	0.00	0.00	0.00
5,000.0	5.80	177.82	4,980.7	-384.1	14.6	384.4	0.00	0.00	0.00
5,100.0	5.80	177.82	5,080.2	-394.2	15.0	394.5	0.00	0.00	0.00
5,200.0	5.80	177.82	5,179.7	-404.3	15.4	404.6	0.00	0.00	0.00

Newfield Exploration

Planning Report

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Lusty 1-11-3-3W
Company:	Newfield Production Company	TVD Reference:	RKB @ 5326.0ft
Project:	Uinta Basin	MD Reference:	RKB @ 5326.0ft
Site:	Lusty 1-11-3-3W	North Reference:	True
Well:	Lusty 1-11-3-3W	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,300.0	5.80	177.82	5,279.2	-414.4	15.8	414.7	0.00	0.00	0.00
5,400.0	5.80	177.82	5,378.6	-424.5	16.2	424.8	0.00	0.00	0.00
5,500.0	5.80	177.82	5,478.1	-434.6	16.5	434.9	0.00	0.00	0.00
5,600.0	5.80	177.82	5,577.6	-444.7	16.9	445.0	0.00	0.00	0.00
5,700.0	5.80	177.82	5,677.1	-454.8	17.3	455.1	0.00	0.00	0.00
5,800.0	5.80	177.82	5,776.6	-464.9	17.7	465.2	0.00	0.00	0.00
5,900.0	5.80	177.82	5,876.1	-475.0	18.1	475.3	0.00	0.00	0.00
6,000.0	5.80	177.82	5,975.6	-485.1	18.5	485.4	0.00	0.00	0.00
6,100.0	5.80	177.82	6,075.1	-495.2	18.8	495.5	0.00	0.00	0.00
6,200.0	5.80	177.82	6,174.6	-505.3	19.2	505.6	0.00	0.00	0.00
6,300.0	5.80	177.82	6,274.0	-515.4	19.6	515.7	0.00	0.00	0.00
6,400.0	5.80	177.82	6,373.5	-525.5	20.0	525.8	0.00	0.00	0.00
6,500.0	5.80	177.82	6,473.0	-535.6	20.4	536.0	0.00	0.00	0.00
6,600.0	5.80	177.82	6,572.5	-545.7	20.8	546.1	0.00	0.00	0.00
6,700.0	5.80	177.82	6,672.0	-555.8	21.2	556.2	0.00	0.00	0.00
6,800.0	5.80	177.82	6,771.5	-565.9	21.5	566.3	0.00	0.00	0.00
6,900.0	5.80	177.82	6,871.0	-576.0	21.9	576.4	0.00	0.00	0.00
7,000.0	5.80	177.82	6,970.5	-586.1	22.3	586.5	0.00	0.00	0.00
7,036.7	5.80	177.82	7,007.0	-589.8	22.5	590.2	0.00	0.00	0.00
7,100.0	3.90	177.82	7,070.0	-595.1	22.7	595.5	3.00	-3.00	0.00
7,200.0	0.90	177.82	7,169.9	-599.3	22.8	599.7	3.00	-3.00	0.00
7,230.1	0.00	0.00	7,200.0	-599.5	22.8	600.0	3.00	-3.00	0.00
7,300.0	0.00	0.00	7,269.9	-599.5	22.8	600.0	0.00	0.00	0.00
7,400.0	0.00	0.00	7,369.9	-599.5	22.8	600.0	0.00	0.00	0.00
7,500.0	0.00	0.00	7,469.9	-599.5	22.8	600.0	0.00	0.00	0.00
7,600.0	0.00	0.00	7,569.9	-599.5	22.8	600.0	0.00	0.00	0.00
7,700.0	0.00	0.00	7,669.9	-599.5	22.8	600.0	0.00	0.00	0.00
7,800.0	0.00	0.00	7,769.9	-599.5	22.8	600.0	0.00	0.00	0.00
7,900.0	0.00	0.00	7,869.9	-599.5	22.8	600.0	0.00	0.00	0.00
8,000.0	0.00	0.00	7,969.9	-599.5	22.8	600.0	0.00	0.00	0.00
8,100.0	0.00	0.00	8,069.9	-599.5	22.8	600.0	0.00	0.00	0.00
8,200.0	0.00	0.00	8,169.9	-599.5	22.8	600.0	0.00	0.00	0.00
8,300.0	0.00	0.00	8,269.9	-599.5	22.8	600.0	0.00	0.00	0.00
8,400.0	0.00	0.00	8,369.9	-599.5	22.8	600.0	0.00	0.00	0.00
8,500.0	0.00	0.00	8,469.9	-599.5	22.8	600.0	0.00	0.00	0.00
8,600.0	0.00	0.00	8,569.9	-599.5	22.8	600.0	0.00	0.00	0.00
8,700.0	0.00	0.00	8,669.9	-599.5	22.8	600.0	0.00	0.00	0.00
8,800.0	0.00	0.00	8,769.9	-599.5	22.8	600.0	0.00	0.00	0.00
8,900.0	0.00	0.00	8,869.9	-599.5	22.8	600.0	0.00	0.00	0.00
9,000.0	0.00	0.00	8,969.9	-599.5	22.8	600.0	0.00	0.00	0.00
9,100.0	0.00	0.00	9,069.9	-599.5	22.8	600.0	0.00	0.00	0.00
9,200.0	0.00	0.00	9,169.9	-599.5	22.8	600.0	0.00	0.00	0.00
9,300.0	0.00	0.00	9,269.9	-599.5	22.8	600.0	0.00	0.00	0.00
9,400.0	0.00	0.00	9,369.9	-599.5	22.8	600.0	0.00	0.00	0.00
9,500.0	0.00	0.00	9,469.9	-599.5	22.8	600.0	0.00	0.00	0.00
9,600.0	0.00	0.00	9,569.9	-599.5	22.8	600.0	0.00	0.00	0.00
9,700.0	0.00	0.00	9,669.9	-599.5	22.8	600.0	0.00	0.00	0.00
9,800.0	0.00	0.00	9,769.9	-599.5	22.8	600.0	0.00	0.00	0.00
9,900.0	0.00	0.00	9,869.9	-599.5	22.8	600.0	0.00	0.00	0.00
10,000.0	0.00	0.00	9,969.9	-599.5	22.8	600.0	0.00	0.00	0.00
10,100.0	0.00	0.00	10,069.9	-599.5	22.8	600.0	0.00	0.00	0.00
10,200.0	0.00	0.00	10,169.9	-599.5	22.8	600.0	0.00	0.00	0.00
10,300.0	0.00	0.00	10,269.9	-599.5	22.8	600.0	0.00	0.00	0.00
10,400.0	0.00	0.00	10,369.9	-599.5	22.8	600.0	0.00	0.00	0.00

Newfield Exploration

Planning Report

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Lusty 1-11-3-3W
Company:	Newfield Production Company	TVD Reference:	RKB @ 5326.0ft
Project:	Uinta Basin	MD Reference:	RKB @ 5326.0ft
Site:	Lusty 1-11-3-3W	North Reference:	True
Well:	Lusty 1-11-3-3W	Survey Calculation Method:	Minimum Curvature
Wellbore:	Wellbore #1		
Design:	Design #1		

Planned Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
10,500.0	0.00	0.00	10,469.9	-599.5	22.8	600.0	0.00	0.00	0.00
10,600.0	0.00	0.00	10,569.9	-599.5	22.8	600.0	0.00	0.00	0.00
10,700.0	0.00	0.00	10,669.9	-599.5	22.8	600.0	0.00	0.00	0.00
10,800.0	0.00	0.00	10,769.9	-599.5	22.8	600.0	0.00	0.00	0.00
10,900.0	0.00	0.00	10,869.9	-599.5	22.8	600.0	0.00	0.00	0.00
11,000.0	0.00	0.00	10,969.9	-599.5	22.8	600.0	0.00	0.00	0.00
11,030.1	0.00	0.00	11,000.0	-599.5	22.8	600.0	0.00	0.00	0.00

Design Targets

Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (m)	Easting (m)	Latitude	Longitude
- hit/miss target									
- Shape									
1-11-3-3W BHL	0.00	0.00	11,000.0	-599.5	22.8	2,212,724.93	611,919.44	40° 14' 31.265 N	110° 11' 4.456 W
- plan hits target center									
- Point									

Formations

Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
8,735.1	8,705.0	Black Shale		0.00	
9,019.1	8,989.0	CP Limes		0.00	
9,316.1	9,286.0	Wasatch		0.00	

**AFFIDAVIT OF EASEMENT, RIGHT-OF-WAY AND
SURFACE USE AGREEMENT**

Greg Boggs personally appeared before me, being duly sworn, deposes and with respect to State of Utah R649-3-34.7 says:

1. My name is Greg Boggs. I am a Landman for Newfield Production Company, whose address is 1001 17th Street, Suite 2000, Denver, CO 80202 ("Newfield").
2. Newfield is the Operator of the proposed Lusty 1-11-3-3WH well with a surface location to be positioned in the NWNENE of Section 11, Township 3 South, Range 3 West, Duchesne County, Utah (the "Drillsite Location" with a bottom hole location in the SESE of Section 11, Township 3 South, Range 3 West, Duchesne County, Utah. The surface owner of the Drillsite Location is David A. Evans and Alicia L. Evans, whose address is HC 64 Box 390, Duchesne, UT 84021 ("Surface Owner").
3. Newfield and the Surface Owner have agreed upon an Easement, Right-of-Way and Surface Use Agreement dated April 10, 2012 covering the Drillsite Location and access to the Drillsite Location.

FURTHER AFFIANT SAYETH NOT.


ACKNOWLEDGEMENT

STATE OF COLORADO §
 §
COUNTY OF DENVER §

Before me, a Notary Public, in and for the State, on this 12th day of April 2012, personally appeared Greg Boggs, to me known to be the identical person who executed the foregoing instrument, and acknowledged to me that he executed the same as his own free and voluntary act and deed for the uses and purposes therein set forth.


Peter Burns
NOTARY PUBLIC

My Commission Expires:




My Commission Expires 8/09/2015

Typical 5M BOP stack configuration



Typical 5M choke manifold configuration



NEWFIELD EXPLORATION COMPANY**WELL PAD INTERFERENCE PLAT****2-11-3-3WH****1-11-3-3W***Pad Location: NENE Section 11, T3S, R3W, U.S.B.&M.**Proposed Access Road**Exist. Drainage***TOP HOLE FOOTAGES**

2-11-3-3WH
 30' FNL & 1120' FEL
 1-11-3-3W
 60' FNL & 1121' FEL

BOTTOM HOLE FOOTAGES

2-11-3-3WH
 660' FSL & 1980' FEL
 1-11-3-3W
 660' FNL & 1109' FEL

**TOP OF PRODUCING
INTERVAL FOOTAGES**

2-11-3-3WH
 660' FNL & 1980' FEL

*Exist. Fence (Typ.)**Exist. Irrigation Ditch
to be Abandoned**Section Line***Proposed Pit****Sec. 2****Sec. 11****2-11-3-3WH****1-11-3-3W***Edge of
Proposed
Pad*

*S52°21'34"W - 1070.98'
 (To Top of Producing Interval)*

*S09°34'05"W - 4670.26'
 (To Bottom Hole)*

*S02°10'48"E - 599.97'
 (To Bottom Hole)*

Note:

Bearings are based
 on GPS Observations.

RELATIVE COORDINATES
From Top Hole to Bottom Hole

WELL	NORTH	EAST
2-11-3-3WH	-4,605'	-776'
1-11-3-3W	-600'	23'


LATITUDE & LONGITUDE
Surface position of Wells (NAD 83)

WELL	LATITUDE	LONGITUDE
2-11-3-3WH	40° 14' 37.19"	110° 11' 04.75"
1-11-3-3W	40° 14' 36.89"	110° 11' 04.75"

SURVEYED BY: S.H. DATE SURVEYED: 04-17-12 VERSION:
 DRAWN BY: R.B.T. DATE DRAWN: 12-14-11 v9
 SCALE: 1" = 60' REVISED: R.B.T. 05-11-12

Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078




RECEIVED: May 15, 2012

NEWFIELD EXPLORATION COMPANY**PROPOSED LOCATION LAYOUT****2-11-3-3WH****1-11-3-3W****Pad Location: NENE Section 11, T3S, R3W, U.S.B.&M.**

SURVEYED BY: S.H.	DATE SURVEYED: 04-17-12	VERSION:
DRAWN BY: R.B.T.	DATE DRAWN: 12-14-11	v9
SCALE: 1" = 60'	REVISED: R.B.T. 05-11-12	

Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: May 15, 2012

NEWFIELD EXPLORATION COMPANY**CROSS SECTIONS****2-11-3-3WH****1-11-3-3W***Pad Location: NENE Section 11, T3S, R3W, U.S.B.&M.*

NOTE:
UNLESS OTHERWISE
NOTED ALL CUT/FILL
SLOPES ARE AT 1.5:1


ESTIMATED EARTHWORK QUANTITIES
(No Shrink or swell adjustments have been used)
(Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	3,830	3,830	Topsoil is not included in Pad Cut Volume	0
PIT	2,670	0		2,670
TOTALS	6,500	3,830	2,540	2,670

SURVEYED BY: S.H.	DATE SURVEYED: 04-17-12	VERSION:
DRAWN BY: R.B.T.	DATE DRAWN: 12-14-11	v9
SCALE: 1" = 60'	REVISED: R.B.T. 05-11-12	

Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078


RECEIVED: May 15, 2012

NEWFIELD EXPLORATION COMPANY**TYPICAL RIG LAYOUT****2-11-3-3WH****1-11-3-3W***Pad Location: NENE Section 11, T3S, R3W, U.S.B.&M.*

SURVEYED BY: S.H.	DATE SURVEYED: 04-17-12	VERSION:
DRAWN BY: R.B.T.	DATE DRAWN: 12-14-11	v9
SCALE: 1" = 60'	REVISED: R.B.T. 05-11-12	



Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: May 15, 2012



API Number: 4301351412
Well Name: Lusty 1-11-3-3W
Township T0.3 . Range R0.3 . Section 11
Meridian: UBM
Operator: NEWFIELD PRODUCTION COMPANY
 Map Prepared:
 Map Produced by Diana Mason

Units	Wells Query
STATUS	Status
ACTIVE	APD - Approved Permit
EXPLORATORY	DRL - Spudded (Drilling Commenced)
GAS STORAGE	GW - Gas Injection
NF PP OIL	GS - Gas Storage
NF SECONDARY	LA - Location Abandoned
PI OIL	LOC - New Location
PP GAS	OPS - Operation Suspended
PP GEOTHERMAL	PA - Plugged Abandoned
PP OIL	PGW - Producing Gas Well
SECONDARY	POW - Producing Oil Well
TERMINATED	RET - Returned APD
Fields	Fields
Unknown	SGW - Shut-in Gas Well
ABANDONED	SOW - Shut-in Oil Well
ACTIVE	TA - Temp. Abandoned
COMBINED	TW - Test Well
INACTIVE	WDW - Water Disposal
STORAGE	WW - Water Injection Well
TERMINATED	WSW - Water Supply Well



Well Name	NEWFIELD PRODUCTION COMPANY Lusty 1-11-3-3W 430135141200			
String	COND	SURF	I1	PROD
Casing Size(in)	14.000	9.625	7.000	4.500
Setting Depth (TVD)	60	1000	8688	11030
Previous Shoe Setting Depth (TVD)	0	60	1000	8688
Max Mud Weight (ppg)	8.3	8.3	9.5	11.5
BOPE Proposed (psi)	0	500	5000	5000
Casing Internal Yield (psi)	1000	3520	9950	10690
Operators Max Anticipated Pressure (psi)	6292			11.0

Calculations	COND String	14.000	"
Max BHP (psi)	.052*Setting Depth*MW=	26	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	19	NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	13	NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	13	NO
Required Casing/BOPE Test Pressure=		60	psi
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient


Calculations	SURF String	9.625	"
Max BHP (psi)	.052*Setting Depth*MW=	432	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	312	YES air drill/diverter
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	212	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	225	NO OK
Required Casing/BOPE Test Pressure=		1000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		60	psi *Assumes 1psi/ft frac gradient

Calculations	I1 String	7.000	"
Max BHP (psi)	.052*Setting Depth*MW=	4292	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	3249	YES
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	2381	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	2601	NO REasonable
Required Casing/BOPE Test Pressure=		5000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		1000	psi *Assumes 1psi/ft frac gradient

Calculations	PROD String	4.500	"
Max BHP (psi)	.052*Setting Depth*MW=	6596	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	5272	NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	4169	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	6081	YES
Required Casing/BOPE Test Pressure=		5000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		8688	psi *Assumes 1psi/ft frac gradient

43013514120000 Lusty 1-11-3-3W

Casing Schematic



Well name:	43013514120000 Lusty 1-11-3-3W	
Operator:	NEWFIELD PRODUCTION COMPANY	
String type:	Surface	Project ID: 43-013-51412
Location:	DUCHESNE COUNTY	

Design parameters:**Collapse**

Mud weight: 8.330 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 88 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 432 ft

Burst

Max anticipated surface pressure: 880 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 1,000 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 877 ft

Non directional string.**Re subsequent strings:**

Next setting depth: 8,658 ft
Next mud weight: 9.500 ppg
Next setting BHP: 4,273 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 1,000 ft
Injection pressure: 1,000 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	1000	9.625	36.00	J-55	LT&C	1000	1000	8.796	8177
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	433	2020	4.669	1000	3520	3.52	36	453	12.58 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: July 18, 2012
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 1000 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	43013514120000 Lusty 1-11-3-3W	
Operator:	NEWFIELD PRODUCTION COMPANY	
String type:	Intermediate	Project ID: 43-013-51412
Location:	DUCESNE COUNTY	

Design parameters:**Collapse**

Mud weight: 9.500 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 195 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,000 ft

Cement top: 3,514 ft

Burst

Max anticipated surface pressure: 4,151 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 6,056 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight.
Neutral point: 7,447 ft

Directional Info - Build & Drop

Kick-off point: 1100 ft
Departure at shoe: 600 ft
Maximum dogleg: 3 °/100ft
Inclination at shoe: 0 °

Re subsequent strings:

Next setting depth: 11,000 ft
Next mud weight: 11.500 ppg
Next setting BHP: 6,571 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 8,658 ft
Injection pressure: 8,658 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	8688	7	26.00	P-110	LT&C	8658	8688	6.151	90312
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	4273	6230	1.458	6056	9950	1.64	225.1	693	3.08 J

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: July 18, 2012
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 8658 ft, a mud weight of 9.5 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	43013514120000 Lusty 1-11-3-3W	
Operator:	NEWFIELD PRODUCTION COMPANY	
String type:	Production Liner	Project ID: 43-013-51412
Location:	DUCHESNE COUNTY	

Design parameters:**Collapse**

Mud weight: 11.500 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 228 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,000 ft

Cement top: 9,147 ft

Burst

Max anticipated surface pressure: 4,151 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 6,571 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight.
Neutral point: 10,595 ft

Liner top: 8,488 ft

Directional Info - Build & Drop

Kick-off point: 1100 ft
Departure at shoe: 600 ft
Maximum dogleg: 0 °/100ft
Inclination at shoe: 0 °

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	2530	4.5	11.60	P-110	LT&C	11000	11030	3.875	12190
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	6571	7580	1.153	6571	10690	1.63	29.3	279	9.51 J

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: July 18, 2012
Salt Lake City, Utah

Remarks:

For this liner string, the top is rounded to the nearest 100 ft. Collapse is based on a vertical depth of 11000 ft, a mud weight of 11.5 ppg. The Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.



July 25, 2012

State of Utah, Division of Oil, Gas and Mining
ATTN: Diana Mason
P.O. Box 145801
Salt Lake City, UT 84114-5801

RE: Directional Drilling
Lusty 1-11-3-3W

Surface Hole: T3S-R3W Section 11: NENE
60' FNL 1121' FEL

At Target: T3S-R3W Section 11: NENE
660' FNL 1109' FEL

Duchesne County, Utah

Dear Ms. Mason:

In conjunction with the filing by Newfield Production Company (NPC) of an Application for Permit to Drill the above referenced well and in accordance with Oil and Gas Conservation Rule R649-3-11, NPC hereby submits this letter as notice of our intention to directionally drill the captioned well.

Newfield has selected the surface location in order mitigate impact on the surface by utilizing a common well pad for the drilling of the captioned well and Lusty 2-11-3-3W well.

Please be aware that NPC and its partners are the owners of 100% of the leasehold interest within a radius of 460' from all points along the intended wellbore, and it is NPC's intent that no portion of the productive interval will be completed in the portions of the wellbore existing nearer than 660' FNL of Section 11, T3S-R3W.

NPC hereby requests our application for permit to drill be granted pursuant to R649-3-11. If you have any questions or require further information, please contact the undersigned at 303-383-4197 or by email at sgillespie@newfield.com. Your consideration in this matter is greatly appreciated.

Sincerely,
Newfield Production Company


A handwritten signature in blue ink, appearing to read "Shane Gillespie".

Shane Gillespie
Landman

T3S, R3W, U.S.B.&M.**NEWFIELD EXPLORATION COMPANY**

WELL LOCATION, 1-11-3-3W, LOCATED AS SHOWN IN THE NE 1/4 NE 1/4 OF SECTION 11, T3S, R3W, U.S.B.&M. DUCHESNE COUNTY, UTAH.

TARGET BOTTOM HOLE, 1-11-3-3W, LOCATED AS SHOWN IN THE NE 1/4 NE 1/4 OF SECTION 11, T3S, R3W, U.S.B.&M. DUCHESNE COUNTY, UTAH.

**NOTES:**

1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.
3. The Bottom of Hole bears S02°10'48"E 599.97' from the Top of Hole.


THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
No. 189377
05-11-12
STACY W.
STEWART
STATE OF UTAH

TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

DATE SURVEYED: 04-17-12	SURVEYED BY: S.H.	VERSION:
DATE DRAWN: 12-14-11	DRAWN BY: R.B.T.	V9
REVISED: 05-11-12 R.B.T.	SCALE: 1" = 1000'	



◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; Elevations are based on an N.G.S. OPUS Correction. LOCATION: LAT. 40°04'09.56" LONG. 110°00'43.28" (Tristate Aluminum Cap) Elev. 5281.57'

1-11-3-3W
(Surface Location) NAD 83
LATITUDE = 40° 14' 36.89"
LONGITUDE = 110° 11' 04.75"

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator NEWFIELD PRODUCTION COMPANY
Well Name Lusty 1-11-3-3W
API Number 43013514120000 **APD No** 5939 **Field/Unit** WILDCAT
Location: 1/4,1/4 NENE **Sec** 11 **Tw** 3.0S **Rng** 3.0W 60 FNL 1121 FEL
GPS Coord (UTM) 569349 4455122 **Surface Owner** David A. Evans & Alicia L. Evans

Participants

T. Eaton, F. Bird, C. Miller, Z. Mc Intyre, J. Henderson– Newfield; C. Jensen,– DOGM ; Dave Evans
 - Surface owner

Regional/Local Setting & Topography

The proposed action is in the Arcadia area in Duchesne County in a river floodplain below the North Myton bench. The location is bordered on 2 sides by the Lake Fork River. Currently the site is productive farm land in use as summer pasture. The city of Myton can be found approximately 8 miles East with Sand Wash Reservoir 3 miles North. The area is characterized by clayey sandy soils with slopes of < 2% and a high water table surrounded by terracing and benches, both North and South, of several different elevations capped by sandstone cliffs over erodible soils consistent with river floodplain profiles. The occasional Butte can also be found. The immediate area is crisscrossed with numerous canals and associated laterals from the Lake Fork and Duchesne Rivers and Lake Boreham. The area has long been used for farming and ranching operations and has recently seen increasing development for petroleum extraction.

Surface Use Plan

Current Surface Use
 Agricultural

New Road Miles	Well Pad	Src Const Material	Surface Formation
1.559	Width 300 Length 400	Offsite	UNTA

Ancillary Facilities N

Waste Management Plan Adequate? Y

Environmental Parameters

Affected Floodplains and/or Wetlands Y

no riparian vegetation or wetland indicator species although in a flood plain

Flora / Fauna

Productive pasture- No or few native plant species

Disturbed soils are not habitat for wild life

Soil Type and Characteristics

silty clays

Erosion Issues N

Sedimentation Issues N**Site Stability Issues** N**Drainage Diversion Required?** N**Berm Required?** Y**Erosion Sedimentation Control Required?** N**Paleo Survey Run?** N **Paleo Potential Observed?** N **Cultural Survey Run?** N **Cultural Resources?** N**Reserve Pit****Site-Specific Factors****Site Ranking**

Distance to Groundwater (feet)		20
Distance to Surface Water (feet)	200 to 300	10
Dist. Nearest Municipal Well (ft)	500 to 1320	10
Distance to Other Wells (feet)	>1320	0
Native Soil Type	Mod permeability	10
Fluid Type	Fresh Water	5
Drill Cuttings	Normal Rock	0
Annual Precipitation (inches)	10 to 20	5
Affected Populations		
Presence Nearby Utility Conduits	Present	15
Final Score		75 1 Sensitivity Level

Characteristics / Requirements

Pit to be dug to a depth of 8'. Pit should be fenced to prevent entry by deer, other wildlife and domestic animals. Pit to be closed within one year after drilling activities are complete.

Closed Loop Mud Required? N **Liner Required?** Y **Liner Thickness** 16 **Pit Underlayment Required?** Y

Other Observations / Comments

Surface owner asked for and was granted some special conditions at the presite;
 Fencing of the entire pad to keep out livestock
 Fencing along the East side of property boundary
 cattle guards at all fenceline crossings
 gate where the access road enters his property
 soils stockpiling to be contained inside the fence

Chris Jensen
Evaluator

5/30/2012
Date / Time

Application for Permit to Drill

Statement of Basis

Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
5939	43013514120000	LOCKED	OW	P	No
Operator	NEWFIELD PRODUCTION COMPANY		Surface Owner-APD	David A. Evans & Alicia L. Evans	
Well Name	Lusty 1-11-3-3W		Unit		
Field	WILDCAT		Type of Work	DRILL	
Location	NENE 11 3S 3W U 60 FNL 1121 FEL GPS Coord (UTM) 569344E 4455107N				

Geologic Statement of Basis

Newfield proposes to set 60' of conductor and 1,000' of surface casing at this location. The base of the moderately saline water at this location is estimated to be at a depth of 1,700'. Air and or fresh water will be used to drill the entire surface hole. A search of Division of Water Rights records shows 12 water wells within a 10,000 foot radius of the center of Section 11. Depth is listed as ranging from 42 to 300 feet. Depth is not listed for 2 wells. Water use is listed as irrigation, stock watering and domestic use. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The surface casing should either be extended to cover the base of the moderately saline ground water or intermediate string casing cement should be brought up to cover it.

Brad Hill
APD Evaluator

6/20/2012
Date / Time

Surface Statement of Basis

Operator has a surface agreement in place with the landowner. I was made aware that some concessions were made to the landowner. Location is proposed in a place that minimizes disruption of farming operations and is within the spacing window. Access road is going enter the North end of pad.

The soil type and topography at present do not combine to pose a significant threat to erosion or sediment/ pollution transport in these regional climate conditions. Construction standards of the Operator appear to be adequate for the proposed purpose. I recognize no special flora or animal species or cultural resources on site that the proposed action may harm. The landowner was invited and was in attendance for the pre-site inspection. The location should be bermed to prevent spills from leaving the confines of the pad. Fencing around the reserve pit will be necessary once the well is drilled to prevent wildlife and livestock from entering. A synthetic liner of 16 mils (minimum) should be utilized in the reserve pit. Fencing of location to protect livestock during drilling and thereafter.

Chris Jensen
Onsite Evaluator

5/30/2012
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils shall be properly installed and maintained in the reserve pit.

RECEIVED: August 02, 2012

Surface	The reserve pit shall be fenced upon completion of drilling operations.
Surface	The well site shall be bermed to prevent fluids from leaving the pad.
Surface	Fencing of location to protect livestock during drilling and thereafter.

CONFIDENTIAL

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 5/15/2012

API NO. ASSIGNED: 43013514120000

WELL NAME: Lusty 1-11-3-3W

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 719-2018

CONTACT: Don Hamilton

PROPOSED LOCATION: NENE 11 030S 030W

Permit Tech Review: ☒

SURFACE: 0060 FNL 1121 FEL

Engineering Review: ☒

BOTTOM: 0660 FNL 1109 FEL

Geology Review: ☒

COUNTY: DUCHESNE

LATITUDE: 40.24354

LONGITUDE: -110.18472

UTM SURF EASTINGS: 569344.00

NORTHINGS: 4455107.00

FIELD NAME: WILDCAT

LEASE TYPE: 4 - Fee

LEASE NUMBER: patented

PROPOSED PRODUCING FORMATION(S): WASATCH

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

☒ PLAT☒ Bond: STATE - B001834☐ Potash☐ Oil Shale 190-5☐ Oil Shale 190-3☐ Oil Shale 190-13☒ Water Permit: 437478☒ RDCC Review: 2012-07-25 00:00:00.0☒ Fee Surface Agreement☐ Intent to Commingle

Commingle Approved

LOCATION AND SITING:

☐ R649-2-3.

Unit:

☐ R649-3-2. General☒ R649-3-3. Exception☒ Drilling Unit

Board Cause No: 139-90

Effective Date: 5/9/2012

Siting: 660' Fr Ext Bndry 1320 Fr wells

☒ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 1 - Exception Location - dmason
5 - Statement of Basis - bhill
10 - Cement Ground Water - hmacdonald
12 - Cement Volume (3) - hmacdonald
15 - Directional - dmason
21 - RDCC - dmason
25 - Surface Casing - hmacdonald

RECEIVED: August 02, 2012



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Lusty 1-11-3-3W
API Well Number: 43013514120000
Lease Number: patented
Surface Owner: FEE (PRIVATE)
Approval Date: 8/2/2012

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of 139-90. The expected producing formation or pool is the WASATCH Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Exception Location:

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

The Application for Permit to Drill has been forwarded to the Resource Development Coordinating Committee for review of this action. The operator will be required to comply with any applicable recommendations resulting from this review. (See attached)

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

The 7" casing string cement shall be brought back to $\pm 800'$ to isolate base of moderately saline ground water.

Cement volume for the 4 1/2 production string shall be determined from actual hole diameter in order to place cement from the pipe setting depth back to 8488' MD as indicated in the submitted drilling plan.

Surface casing shall be cemented to the surface.

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan - contact Dustin Doucet
- Significant plug back of the well - contact Dustin Doucet
- Plug and abandonment of the well - contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website
at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program
- contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well - contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation

- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

BLM - Vernal Field Office - Notification Form

CONFIDENTIAL

Operator Newfield Exploration Rig Name/# Ross 31 Submitted By
Branden Arnold Phone Number 435-401-0223
Well Name/Number Lusty 1-11-3-3W
Qtr/Qtr NE/NE Section 11 Township 3S Range 3W
Lease Serial Number Patented
API Number 43-013-51412

Spud Notice – Spud is the initial spudding of the well, not drilling
out below a casing string.

Date/Time 9/24/12 8:00 AM ☒ PM ☐

Casing – Please report time casing run starts, not cementing
times.

- ☒ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 9/24/12 2:00 AM ☐ PM ☒

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time _____ AM ☐ PM ☐

Remarks _____

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Ross 26 Submitted By
Branden Arnold Phone Number 4354010223
Well Name/Number Lusty 1-11-3-3W
Qtr/Qtr NENE Section 11 Township 3 Range 3W
Lease Serial Number patented
API Number 43-013514120000

Spud Notice – Spud is the initial spudding of the well, not drilling
out below a casing string.

Date/Time 9/28/12 10 AM ☒ PM ☐

Casing – Please report time casing run starts, not cementing
times.

- ☒ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 9/29/12 12 AM ☒ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time _____ AM ☐ PM ☐

Remarks _____

Alexis Huefner - Newfield - Lusty 1-11-3-3W Spud Notice

From: "Pioneer 68" <den_pio68@nfxrig.com>
To: "Alexis Huefner" <alexishuefner@utah.gov>, "Carol Daniels" <caroldaniels...
Date: 10/3/2012 1:45 PM
Subject: Newfield - Lusty 1-11-3-3W Spud Notice
CC: "Hans Wychgram" <hwychgram@newfield.com>, "Mitch Benson" <mbenson@newfie...

Operator: Newfield Production Company
Well Name: Lusty 1-11-3-3W
Rig: Pioneer #68
Legals: 60' FNL, 1121' FEL, Sec. 11-T3S-R3W
Duchesne County, Utah
API #: 43-013-51412-0000
Contact: See Below

CONFIDENTIAL

Est. Spud 20:00 10/3/2012
Est. Run 9 5/8" Csg: 20:00 10/4/2012
Est. Cement: 23:00 10/4/2012
Est. BOP Test: 05:00 10/5/2012

NEWFIELD



Richard McNeill
Newfield Drilling Supervisor
Pioneer 68
Office 970 361-3263
Cell 720 339-7239
den_pio68@nfxrig.com

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER		5. LEASE DESIGNATION AND SERIAL NUMBER: FEE
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME: UINTA CB - WASATCH DEEP
PHONE NUMBER 435.646.3721		8. WELL NAME and NUMBER: LUSTY 1-11-3-3W
4. LOCATION OF WELL: FOOTAGES AT SURFACE:		9. API NUMBER: 4301351412
OTR/OTR. SECTION, TOWNSHIP, RANGE, MERIDIAN: NENE, 11, T3S, R3W		10. FIELD AND POOL, OR WILDCAT: UINTA CENTRAL BASIN
		COUNTY: DUCHESNE
		STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 09/30/2012	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Spud Notice
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On 9/28/12 MIRU Ross #26. Spud well @6:00 PM. Drill 68' of 17 1/2" hole with air mist. TIH W/ 2 Jt's 14" H-40 36.75# csgn. Set @ 86.
On 9/30/12 cement with 90 sks of class "G" w/ 2% CaCL2 + 0.25#/sk Cello- Flake Mixed @ 15.8ppg w/ 1.17ft3/sk yield. Returned 5 barrels cement to pit. WOC.

CONFIDENTIAL

NAME (PLEASE PRINT) <u>Branden Arnold</u>	TITLE _____
SIGNATURE <u><i>Branden Arnold</i></u>	DATE <u>10/02/2012</u>

(This space for State use only)

RECEIVED
OCT 05 2012
DIV. OF OIL, GAS & MINING

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

OPERATOR: **NEWFIELD PRODUCTION COMPANY**
ADDRESS: **RT. 3 BOX 3630**
MYTON, UT 84052

OPERATOR ACCT NO **N2695**

ACTION CODE	CURRENT ENTITY NO	NEW ENTITY NO	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	17400	4301350880	GMBU 8-14T-9-16	SENE	14	9S	16E	DUCHESNE	9/13/2012	10/24/12
WELL COMMENTS GRRV											
A	99999	18753	4301351390	MORRILL 4-23-3-2WH	NWNW	23	3S	2W	DUCHESNE	9/11/2012	10/24/12
WELL COMMENTS GRRV											
B	99999	17400	4301350821	GMBU Y-35-8-17	NENE	3	9S	17E	DUCHESNE	9/26/2012	10/24/12
WELL COMMENTS GRRV This well's range is 9S-17E at the surface of the whole, and 8S-17E at the bottom of the whole BHL: 8S-17E SWSW											
B	99999	17400	4301351174	GMBU O-10-9-16	SENE	9	9S	16E	DUCHESNE	9/29/2012	10/24/12
WELL COMMENTS GRRV S10 NWSW											
B	99999	17400	4301351173	GMBU L-9-9-16	SENE	9	9S	16E	DUCHESNE	9/18/2012	10/24/12
WELL COMMENTS GRRV BHL: NWSE											
A	99999	18754	4301351412	LUSTY 1-11-3-3W	NENE	11	3S	3W	DUCHESNE	9/28/2012	10/24/12
WELL COMMENTS WSTC NENE											
B	99999	17400	4301351249	GMBU E-16-9-17	SESE	8	9S	17E	DUCHESNE	10/1/2012	10/24/12
WELL COMMENTS GRRV BHL: 16 NWNW											

- A - Establish new entity for new well (single well only)
B - Add new well to existing entity (group or unit well)
C - Re assign well from one existing entity to another existing entity
D - Re assign well from one existing entity to a new entity
E - Other (explain in Comments section)

RECEIVED

OCT 12 2012

Tasha Robison
Signature

Tasha Robison

Production Clerk

10/03/12

NOTE: Use COMMENT section to explain why each Action Code was selected

Div. of Oil, Gas & Mining

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB NO. 1004-0137
Expires: October 31, 2014

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Dry <input type="checkbox"/> Other b. Type of Completion: <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Work Over <input type="checkbox"/> Deepen <input type="checkbox"/> Plug Back <input type="checkbox"/> Diff. Resvr., Other: _____						5. Lease Serial No. PATENTED			
2. Name of Operator NEWFIELD PRODUCTION COMPANY						6. If Indian, Allottee or Tribe Name 			
3. Address ROUTE #3 BOX 3630 MYTON, UT 84052				3a. Phone No. (include area code) Ph:435-646-3721		7. Unit or CA Agreement Name and No. 			
4. Location of Well (Report location clearly and in accordance with Federal requirements)* At surface 60' FNL 1121' FEL (NE/NE) SEC 11 T3S R3W At top prod. interval reported below 710' FNL 1091' FEL (NE/NE) SEC 11 T3S R3W 750' FNL 1094' FEL (NE/NE) SEC 11 T3S R3W At total depth						8. Lease Name and Well No. LUSTY 1-11-3-3W			
14. Date Spudded 09/28/2012		15. Date T.D. Reached 10/18/2012		16. Date Completed 03/16/2013 <input type="checkbox"/> D & A <input checked="" type="checkbox"/> Ready to Prod.		9. API Well No. 43-013-51412			
18. Total Depth: MD 10670' TVD 10638'		19. Plug Back T.D.: MD 10613' TVD		20. Depth Bridge Plug Set: MD TVD		17. Elevations (DF, RKB, RT, GL)* 5307' GL 5325' KB			
21. Type Electric & Other Mechanical Logs Run (Submit copy of each) DUAL IND GRD, SP, COMP. NEUTRON, GR, CALIPER, CMT BOND						22. Was well cored? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Was DST run? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit report) Directional Survey? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes (Submit copy)			
23. Casing and Liner Record (Report all strings set in well)									
Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cementer Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
13-1/2"	9-5/8" J-55	36	0'	1011'		456 CLASS G			
8-7/8"	7" P-110	26	0'	8628'		300 Bondcem		0'	
						715 Versacem			
6-1/4"	4.5" P-110	13.5	8298'	10655'		210 Versacem			
24. Tubing Record									
Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	
2-7/8"	EOT@8803'								
25. Producing Intervals									
Formation		Top	Bottom	Perforated Interval		Size	No. Holes	Perf. Status	
A) Green River		8852'	8876'	8852' - 8876' MD		0.34	27		
B) Wasatch		9356'	10159'	9356' - 10159' MD		0.34	99		
C)									
D)									
26. Perforation Record									
27. Acid, Fracture, Treatment, Cement Squeeze, etc.									
Depth Interval		Amount and Type of Material							
8852' - 10159' MD		Frac w/667,699#s of 20/40 white sand and 63,880 super LC 20/40 in 14,713 bbls of Lightning 17 fluid, in 5 stages.							
28. Production - Interval A									
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
1/1/2013	1/10/13	24	→	575	506	1950			GAS LIFT
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→					PRODUCING	
28a. Production - Interval B									
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

*(See instructions and spaces for additional data on page 2)

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

29. Disposition of Gas (Solid, used for fuel, vented, etc.)

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

GEOLOGICAL MARKERS

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				GARDEN GULCH MARK GARDEN GULCH 1	6793' 7072'
				GARDEN GULCH 2 DOUGLAS CREEK	7238' 7883'
				CASTLE PEAK UTELAND BUTTE	8790' 9093'
				WASATCH WASATCH 10	9238' 9406'
				WASATCH 30	10085'

32. Additional remarks (include plugging procedure):

33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☐ Electrical/Mechanical Logs (1 full set req'd.)
 ☐ Geologic Report
 ☐ DST Report
 ☒ Directional Survey
☐ Sundry Notice for plugging and cement verification
 ☐ Core Analysis
 ☒ Other: Drilling daily activity

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Heather Calder

Title Regulatory Technician

Signature

Heather Calder

Date 04/02/2014

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 3)

(Form 3160-4, page 2)



Weatherford®

NEWFIELD EXPLORATION CO.

DUCHESNE COUNTY, UT

LUSTY 1-11-3-3W

LUSTY 1-11-3-3W

LUSTY 1-11-3-3W

Survey: Survey #1

Standard Survey Report

16 October, 2012



Weatherford®



Weatherford

Weatherford

Company:	NEWFIELD EXPLORATION CO.	Local Co-ordinate Reference:	Well LUSTY 1-11-3-3W
Project:	DUCHESNE COUNTY, UT	TVD Reference:	WELL @ 5324.80ft (Original Well Elev)
Site:	LUSTY 1-11-3-3W	MD Reference:	WELL @ 5324.80ft (Original Well Elev)
Well:	LUSTY 1-11-3-3W	North Reference:	True
Wellbore:	LUSTY 1-11-3-3W	Survey Calculation Method:	Minimum Curvature
Design:	LUSTY 1-11-3-3W	Database:	EDM 5000.1 Single User Db

Project	DUCHESNE COUNTY, UT		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Central Zone		

Site	LUSTY 1-11-3-3W				
Site Position:		Northing:	7,260,150.48 usft	Latitude:	40° 14' 36.890 N
From:	Lat/Long	Easting:	2,007,574.50 usft	Longitude:	110° 11' 4.750 W
Position Uncertainty:	0.00 ft	Slot Radius:	13-3/16"	Grid Convergence:	0.84 °

Well	LUSTY 1-11-3-3W					
Well Position	+N/-S	0.00 ft	Northing:	7,260,150.48 usft	Latitude:	40° 14' 36.890 N
	+E/-W	0.00 ft	Easting:	2,007,574.50 usft	Longitude:	110° 11' 4.750 W
Position Uncertainty	0.00 ft	Wellhead Elevation:	ft	Ground Level:	5,306.80 ft	

Wellbore	LUSTY 1-11-3-3W				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	BGGM2012	9/26/2012	11.26	65.88	52,179

Design	LUSTY 1-11-3-3W				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W	Direction	
	(ft)	(ft)	(ft)	(°)	
	0.00	0.00	0.00	177.81	

Survey Program		Date	10/16/2012		
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
170.00	10,670.00	Survey #1 (LUSTY 1-11-3-3W)	MWD	MWD - Standard	

Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
170.00	0.58	64.54	170.00	0.37	0.78	-0.34	0.34	0.34	0.00
261.00	0.82	49.73	260.99	0.99	1.69	-0.92	0.33	0.26	-16.27
352.00	1.05	59.21	351.98	1.84	2.90	-1.72	0.30	0.25	10.42
474.00	1.68	63.04	473.94	3.22	5.46	-3.01	0.52	0.52	3.14
595.00	0.63	165.85	594.92	3.38	7.20	-3.10	1.59	-0.87	84.97
751.00	0.90	178.50	750.91	1.32	7.44	-1.04	0.20	0.17	8.11
878.00	1.26	169.10	877.89	-1.05	7.73	1.34	0.32	0.28	-7.40
957.00	1.24	172.81	956.87	-2.75	8.00	3.05	0.11	-0.03	4.70
1,045.00	1.61	165.11	1,044.84	-4.89	8.44	5.20	0.47	0.42	-8.75
1,117.00	1.65	164.38	1,116.81	-6.86	8.98	7.20	0.06	0.06	-1.01
1,200.00	3.01	186.24	1,199.74	-10.18	9.06	10.52	1.93	1.64	26.34
1,295.00	4.88	187.53	1,294.51	-16.67	8.26	16.97	1.97	1.97	1.36



Weatherford International Ltd.

Survey Report



Weatherford

Company: NEWFIELD EXPLORATION CO.
Project: DUCHESNE COUNTY, UT
Site: LUSTY 1-11-3-3W
Well: LUSTY 1-11-3-3W
Wellbore: LUSTY 1-11-3-3W
Design: LUSTY 1-11-3-3W

Local Co-ordinate Reference: Well LUSTY 1-11-3-3W
TVD Reference: WELL @ 5324.80ft (Original Well Elev)
MD Reference: WELL @ 5324.80ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
1,421.00	4.56	186.13	1,420.09	-26.96	7.03	27.21	0.27	-0.25	-1.11
1,548.00	5.91	182.19	1,546.55	-38.51	6.24	38.72	1.10	1.06	-3.10
1,675.00	5.38	179.26	1,672.94	-51.00	6.06	51.19	0.47	-0.42	-2.31
1,801.00	6.46	179.75	1,798.26	-63.99	6.17	64.18	0.86	0.86	0.39
1,928.00	6.27	180.16	1,924.48	-78.07	6.18	78.25	0.15	-0.15	0.32
2,054.00	5.93	179.23	2,049.77	-91.46	6.25	91.63	0.28	-0.27	-0.74
2,181.00	5.92	179.49	2,176.09	-104.57	6.40	104.74	0.02	-0.01	0.20
2,307.00	5.88	179.42	2,301.42	-117.52	6.52	117.69	0.03	-0.03	-0.06
2,434.00	5.72	176.55	2,427.77	-130.34	6.97	130.52	0.26	-0.13	-2.26
2,560.00	6.24	178.69	2,553.09	-143.46	7.50	143.64	0.45	0.41	1.70
2,686.00	6.35	177.70	2,678.33	-157.27	7.94	157.46	0.12	0.09	-0.79
2,813.00	6.26	176.31	2,804.56	-171.19	8.67	171.40	0.14	-0.07	-1.09
2,939.00	6.41	177.10	2,929.79	-185.07	9.46	185.30	0.14	0.12	0.63
3,066.00	6.36	175.23	3,056.00	-199.16	10.41	199.42	0.17	-0.04	-1.47
3,193.00	6.36	174.84	3,182.22	-213.18	11.63	213.47	0.03	0.00	-0.31
3,319.00	7.01	178.71	3,307.36	-227.82	12.43	228.13	0.63	0.52	3.07
3,446.00	6.91	177.88	3,433.43	-243.20	12.88	243.51	0.11	-0.08	-0.65
3,572.00	6.70	176.82	3,558.54	-258.11	13.57	258.44	0.19	-0.17	-0.84
3,698.00	6.05	173.22	3,683.76	-272.05	14.76	272.41	0.61	-0.52	-2.86
3,825.00	6.51	179.31	3,810.00	-285.89	15.64	286.28	0.64	0.36	4.80
3,951.00	6.32	178.96	3,935.21	-299.97	15.85	300.35	0.15	-0.15	-0.28
4,078.00	5.41	178.06	4,061.54	-312.94	16.18	313.33	0.72	-0.72	-0.71
4,204.00	5.85	177.18	4,186.94	-325.29	16.70	325.69	0.36	0.35	-0.70
4,331.00	6.36	179.70	4,313.22	-338.79	17.05	339.19	0.45	0.40	1.98
4,457.00	5.63	179.65	4,438.53	-351.95	17.13	352.34	0.58	-0.58	-0.04
4,583.00	6.28	179.88	4,563.85	-365.02	17.18	365.41	0.52	0.52	0.18
4,710.00	5.49	178.14	4,690.18	-378.04	17.39	378.43	0.64	-0.62	-1.37
4,836.00	5.68	177.84	4,815.58	-390.29	17.82	390.69	0.15	0.15	-0.24
4,899.00	6.25	179.13	4,878.24	-396.84	17.99	397.23	0.93	0.90	2.05
5,025.00	6.01	179.00	5,003.52	-410.29	18.21	410.69	0.19	-0.19	-0.10
5,151.00	4.79	175.95	5,128.95	-422.13	18.70	422.54	0.99	-0.97	-2.42
5,278.00	5.94	178.49	5,255.40	-433.99	19.25	434.41	0.92	0.91	2.00
5,404.00	5.84	176.62	5,380.73	-446.91	19.80	447.34	0.17	-0.08	-1.48
5,530.00	7.23	179.78	5,505.91	-461.24	20.20	461.67	1.14	1.10	2.51
5,656.00	5.83	176.05	5,631.09	-475.55	20.68	475.99	1.16	-1.11	-2.96
5,782.00	6.28	181.43	5,756.39	-488.82	20.94	489.27	0.57	0.36	4.27
5,908.00	6.64	177.27	5,881.59	-502.99	21.12	503.43	0.47	0.29	-3.30
6,034.00	6.00	176.59	6,006.82	-516.84	21.86	517.30	0.51	-0.51	-0.54
6,161.00	5.51	174.25	6,133.18	-529.53	22.86	530.02	0.43	-0.39	-1.84
6,287.00	6.05	179.04	6,258.54	-542.19	23.58	542.70	0.57	0.43	3.80
6,414.00	5.23	177.72	6,384.92	-554.67	23.92	555.18	0.65	-0.65	-1.04
6,540.00	4.84	175.38	6,510.44	-565.70	24.58	566.23	0.35	-0.31	-1.86
6,667.00	4.59	175.48	6,637.01	-576.11	25.41	576.66	0.20	-0.20	0.08
6,793.00	4.16	175.63	6,762.64	-585.69	26.16	586.26	0.34	-0.34	0.12
6,920.00	3.91	176.13	6,889.33	-594.60	26.80	595.19	0.20	-0.20	0.39
7,047.00	3.65	176.15	7,016.05	-602.96	27.36	603.56	0.20	-0.20	0.02
7,173.00	2.38	173.28	7,141.87	-609.56	27.94	610.18	1.01	-1.01	-2.28
7,300.00	1.50	174.47	7,268.80	-613.83	28.41	614.47	0.69	-0.69	0.94
7,426.00	1.94	174.96	7,394.74	-617.60	28.75	618.25	0.35	0.35	0.39
7,553.00	1.75	168.19	7,521.68	-621.64	29.34	622.30	0.23	-0.15	-5.33
7,680.00	2.16	168.68	7,648.60	-625.88	30.21	626.58	0.32	0.32	0.39
7,806.00	1.61	154.02	7,774.53	-629.80	31.45	630.54	0.58	-0.44	-11.63
7,933.00	0.50	110.56	7,901.51	-631.60	32.75	632.39	1.02	-0.87	-34.22
8,059.00	1.22	169.05	8,027.50	-633.11	33.52	633.93	0.83	0.57	46.42

**Weatherford****Weatherford**

Company: NEWFIELD EXPLORATION CO.
Project: DUCHESNE COUNTY, UT
Site: LUSTY 1-11-3-3W
Well: LUSTY 1-11-3-3W
Wellbore: LUSTY 1-11-3-3W
Design: LUSTY 1-11-3-3W

Local Co-ordinate Reference: Well LUSTY 1-11-3-3W
TVD Reference: WELL @ 5324.80ft (Original Well Elev)
MD Reference: WELL @ 5324.80ft (Original Well Elev)
North Reference: True
Survey Calculation Method: Minimum Curvature
Database: EDM 5000.1 Single User Db

Survey

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
8,186.00	2.41	170.17	8,154.43	-637.07	34.23	637.91	0.94	0.94	0.88
8,313.00	1.84	182.53	8,281.35	-641.74	34.60	642.59	0.57	-0.45	9.73
8,439.00	1.34	213.40	8,407.30	-644.99	33.70	645.80	0.77	-0.40	24.50
8,565.00	0.49	267.92	8,533.28	-646.24	32.35	647.00	0.90	-0.67	43.27
8,595.00	0.60	254.93	8,563.28	-646.28	32.07	647.04	0.55	0.37	-43.30
8,708.00	0.98	211.49	8,676.27	-647.26	30.99	647.97	0.60	0.34	-38.44
8,835.00	1.29	199.46	8,803.25	-649.53	29.95	650.20	0.31	0.24	-9.47
8,962.00	1.34	192.75	8,930.21	-652.33	29.14	652.97	0.13	0.04	-5.28
9,088.00	1.54	183.54	9,056.17	-655.46	28.71	656.08	0.24	0.16	-7.31
9,215.00	1.73	184.82	9,183.12	-659.07	28.45	659.68	0.15	0.15	1.01
9,342.00	0.36	189.13	9,310.10	-661.38	28.22	661.97	1.08	-1.08	3.39
9,468.00	0.91	177.41	9,436.09	-662.77	28.21	663.36	0.45	0.44	-9.30
9,594.00	1.02	176.35	9,562.07	-664.88	28.32	665.48	0.09	0.09	-0.84
9,720.00	0.50	177.66	9,688.06	-666.55	28.42	667.15	0.41	-0.41	1.04
9,847.00	0.98	183.27	9,815.05	-668.19	28.38	668.79	0.38	0.38	4.42
9,974.00	1.38	185.10	9,942.02	-670.80	28.18	671.39	0.32	0.31	1.44
10,101.00	1.55	188.46	10,068.98	-674.02	27.79	674.59	0.15	0.13	2.65
10,228.00	1.58	181.14	10,195.93	-677.47	27.50	678.03	0.16	0.02	-5.76
10,355.00	1.42	183.94	10,322.89	-680.79	27.36	681.34	0.14	-0.13	2.20
10,482.00	1.68	181.90	10,449.84	-684.22	27.19	684.76	0.21	0.20	-1.61
LAST SVY									
10,614.00	1.99	177.70	10,581.78	-688.45	27.22	688.98	0.26	0.23	-3.18
PROJ SVY - PBHL LUSTY 1-11-3-3W									
10,670.00	1.99	177.70	10,637.74	-690.39	27.30	690.93	0.00	0.00	0.00

Survey Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment
		+N/-S (ft)	+E/-W (ft)	
10,614.00	10,581.78	-688.45	27.22	LAST SVY
10,670.00	10,637.74	-690.39	27.30	PROJ SVY

Checked By: _____ Approved By: _____ Date: _____

Daily Activity Report

Format For Sundry
LUSTY 1-11-3-3W
11/1/2012 To 3/28/2013

11/20/2012 Day: 1**Completion**

Rigless on 11/20/2012 - Install Tbg Head and test - Conduct PJSM. Have back hoe, Grader and dress and clean location. Placed gravel in cellar and fill mouse hole. Set Outback or Select office trailer, trash bin and Pot-a-Pots. MIRU B&G crane and install Cameron Tbg head. Test void 5000 psi. Test wing valves 250 psi low and 5,000 psi high. 5min and 10 min. all tested good. Install FMC 10KHCR frac valve and test 250 low and 10,000 psi high. All test charted on file. Shut well in and cap.

Daily Cost: \$0

Cumulative Cost: \$10,806

11/21/2012 Day: 2**Completion**

Rigless on 11/21/2012 - Shut in well, work suspended until later date - PU and RIH w/ 3.75" Gauge Ring and tag liner top @ +/- 8291 WLM. Lost tool weight and on PU "sticky". Decision to POOH and RDWL. - MIRU JW WL

Daily Cost: \$0

Cumulative Cost: \$32,857

11/30/2012 Day: 3**Completion**

Rigless on 11/30/2012 - MIRU Mountain state WOR, NU 5K BOP stack, Spot Pipe rick, and tally tbg - MIRU Mountain state WOR. 15:00 to 17:00 Mountain state is RU waiting on 5K BOP stack from Night oil tool. Deliver time should be around 18:30 PM. - Well shut in no activity. - PUMU Knight Oil tools 5k 71/16? BOP stack, NU 10K X 5K companion spool, 71/16? 5K Double BOP with blind rams and 2 3/8 pipe rams, 71/16? 5K flow cross with double outlets with double valve, single 7 1/16? 5K BOP with 2 3/8 pipe rams, and Washington stripper head.

Daily Cost: \$0

Cumulative Cost: \$55,053

12/1/2012 Day: 4**Completion**

Rigless on 12/1/2012 - NU Knight's BOP's and test, PUMU RIH 3.75 claw mill, C/O 10,607', POH L/D PH6 tbg, MIRU W/L for CBL logs, - 20:30 ? 00:00 MIRU JW Wireline to run 3.750? gauge ring and CBL logs from surface to PBTD 10,606?. RU 5-1/2" 5K lubricator, PU 3.750? gage ring and junk basket and make-up lubricator. Function test both wireline rams. Test lubricator to 5,000 psi for 5 minutes against upper manual frac valve with no pressure departure. RIH 3.750? gage ring and junk basket to PBTD 10,613? (WLM), POH with gage ring, all tools recovered. - 11:30 -15:15 RU power swivel and clean fill @ 10,580? FS. Start pumping Clean out fill @ 2 BMP @ 8,00 psi. Drill out cement from 10,580? to 10,607 on top float collar. Total water used 225 bbls water. RD Power swivel and LD 338 jts 2-38? tbg 5.95# PH-6, 1- ?R? nipple, 1 jts 2-3/8? PH-6 5.95#, 1.867 ID, ?RN nipple, Crossover, bit sub, claw mill 3.75? OD. - 07:00 ? 08:30 PUMU 3.750? OD clog mill, Bit sub, crossover, ?RN? nipple, 1 jts of 2 3/8 PH6 P110 5.95# 1.867 ID, ?R? nipple, 2 jts of 2 3/8 PH6 P110 5.95# 1.867 ID, (liner top @8,298?). Did not tag anything through the top of the liner hanger at 8,298?FS. We are proceeding to, TIH w/2-3/8? PH-6 5.95# 1.867 ID, to Float collar and circulate bottoms up. 08:00 ? 11:30 AM RIH w/ 3.750? OD clog mill, Bit sub, crossover, ?RN? nipple, 1 jts of 2

3/8 PH6 P110 5.95# 1.867 ID, ?R? nipple, 336 jts of 2 3/8 PH6 P110 5.95# 1.867 ID, (Tag hard fill @10.580?) Start Cir Hole @ 2 BMP @ 8,00 psi after, recover 61 bbls water we recover 5 bbls of drill mud back. We pump total 195 bbls water and shut down . Had order from the office clean out to 10,607. RU power Swivel - PUMU Knight Oil tools 5k 71/16? BOP stack, NU on 10K manual frac valve, 7 1/16? 10K X 5K companion spool, 71/16? 5K Double BOP with blind rams and 2 3/8 pipe rams, 71/16? 5K flow cross with double outlets with double valve, single 7 1/16? 5K BOP with 2 3/8 pipe rams, and Washington stripper head. Test stack to 4,500 psi, Tested each of stack. - PUMU Knight Oil tools 5k 71/16? BOP stack, NU on 10K manual frac valve, 7 1/16? 10K X 5K companion spool, 71/16? 5K Double BOP with blind rams and 2 3/8 pipe rams, 71/16? 5K flow cross with double outlets with double valve, single 7 1/16? 5K BOP with 2 3/8 pipe rams, and Washington stripper head. Test stack to 4,500 psi, Tested each part of stack.

Daily Cost: \$0

Cumulative Cost: \$81,478

12/2/2012 Day: 5

Completion

Rigless on 12/2/2012 - RIH and run CBL logs, RN BOP Stack instal TWVC w/2-7/8" tbg hanger Pressure test casing - ND night oil tools 5K bop stack, install 2-7/8? tbg hanger w/TWCV and install Weatherford 10K night cap. Start pressure on the casing to 8,000 psi for 30 min. Good test. Billed of casing and monitor for 10 min, and chart test. No departure allowed. - Well shut no activity - PUMU CBL logging tool and make-up lubricator. Test lubricator to 5,000 psi for 5 minutes against upper manual frac valve with no pressure departure. RIH CBL logging tool to PBTD 10,613? (WLM), Run CBL at 0 psi from PBTD to cement top in 7" casing. Note 0 psi on the well for CBL on header of log. RIH and log CBL from PBTD 10,613? to 8,000 ft with 1,000 psi on wellhead. Note 1,000 psi on the well for CBL on header of log. POH with CBL logging tools, all tools recovered.All log is complete, RDMO J&W wireline.

Daily Cost: \$0

Cumulative Cost: \$113,550

12/6/2012 Day: 6

Completion

Rigless on 12/6/2012 - Close in well, no activity - MIRU FMC test Unit. Deadhead against test unit to 10,000 psi, for 5 min. Test Ok. PT body 10,000 psi high 10 minuntes, 300 psi low for 5 minutes, PT 2 1/16" wing valves 10,000 psi high 10 minutes, 300 psi low for 5 minutes. Negative test lower 7 1/16" frac valve 10,000 psi high 10 minutes 300 psi low 5 minutes, Middle Master 7 1/16" 10,000 psi high 10 min 300 psi lower 5 minutes, Upper master 7 1/16" 10,000 psi high 10 minutes 300 psi low 5 minutes. RD FMC test unit. Close in well - 1400 MIRU JW Crane. FMC on location w/7-1/16" 10K frac stack. NU FMC 7-1/16' 10K x 10K adaptor spool, 7-1/16' 10K manual frac valve, Flow cross w/dual, double 2-1/16" outlets. Bled casing off. Remove 7-1/16" x 2-7/8" tbg hanger w/TWCV. Continue to NU manual frac valve. Plan is to NU frac stack, test same. - No Activity

Daily Cost: \$0

Cumulative Cost: \$129,369

12/7/2012 Day: 7

Completion

Rigless on 12/7/2012 - No Activity - No Activity

Daily Cost: \$0

Cumulative Cost: \$130,219

12/8/2012 Day: 8

Completion

Rigless on 12/8/2012 - No Activity - No Activity

Daily Cost: \$0

Cumulative Cost: \$131,069

12/9/2012 Day: 9**Completion**

Rigless on 12/9/2012 - No Activity - No Activity

Daily Cost: \$0

Cumulative Cost: \$131,919

12/10/2012 Day: 10**Completion**

Rigless on 12/10/2012 - No Activity - No Activity

Daily Cost: \$0

Cumulative Cost: \$144,042

12/11/2012 Day: 11**Completion**

Rigless on 12/11/2012 - MIRU Pennacle/Halliburton Microseismic Tools, Haul in KCL water for frac. - Hauling in 5000 Bbls KCL frac fluid - Tool #13 DDS-250 Down hole Shuttle Channel (V,H1, H2) 39, 38, 37: 2.500? OD x 36.9? long, 2 Rigid Interconnect: 2.500? OD x 36.9? long, Tool #12 DDS-250 Down hole Shuttle Channel (V,H1, H2) 36, 35, 34: 2.500? OD x 36.9? long, 2 Rigid Interconnect: 2.500? OD x 36.9? long, Tool #11, 10, 9 DDS-250 Down hole Shuttle Channel (V,H1, H2) 33, 32, 31, 30, 29, 28, 27, 26, 25: 2.500? OD x 36.9? long, 2 Rigid Interconnect: 2.500? OD x 36.9? long, Tool #8 DDS-250 Down hole Shuttle Channel (V,H1, H2) 24, 23, 22: 2.500? OD x 36.9? long, 2 Rigid Interconnect: 2.500? OD x 36.9? long, Tool #7 DDS-250 Down hole Shuttle Channel (V,H1, H2) 21, 20, 19: 2.500? OD x 36.9? long, , 1 Flexible Wireline Cable Interconnect: 2.500? OD x 39.4? long, Tool #6 DDS-250 Down hole Shuttle Channel (V,H1, H2) 18, 17, 16: 2.500? OD x 36.9? long, 1 Flexible Wireline Cable Interconnect: 2.500? OD x 39.4? long, Tool #5, 4, 3 DDS-250 Down hole Shuttle Channel (V,H1, H2) 15, 14, 13, 12, 11, 10, 9, 8, 7: 2.500? OD x 36.9? long, 2 Flexible Wireline Cable Interconnect: 2.500? OD x 39.4? long, Tool #2 DDS-250 Down hole Shuttle Channel (V,H1, H2) 6, 5, 4: 2.500? OD x 36.9? long, 2 Flexible Wireline Cable Interconnect: 2.500? OD x 73.7? long, Tool #1 DDS-250 Down hole Shuttle Channel (V,H1, H2) 3, 2, 1: 2.500? OD x 36.9? long, Cable Head: 2.500? OD x 4.0? long. RIH to 300?. EOT @ 980.10? ?WLM?. 9 (Total length 680.10?) Standby for frac date. Continue to Haul KCL water to fill frac tanks. - NU 10K 7-1/16? x 5K adaptor spool, 5K 7-1/16? WL flange. TIH w/CCL 2.500? OD x 4? long, Tool #24 DDS-250 Down hole Shuttle Channel (V,H1, H2) 72, 71, 70: 2.500? OD x 36.9? long, 2 Rigid Interconnect: 2.500? OD x 36.9? long, Tool #23, 22, 21 DDS-250 Down hole Shuttle Channel (V,H1, H2) 69, 68, 67, 66, 65, 64, 63, 62, 61: 2.500? OD x 36.9? long, , 2 Rigid Interconnect: 2.500? OD x 36.9? long, Tool #20 DDS-250 Down hole Shuttle Channel (V,H1, H2) 60, 59, 58: 2.500? OD x 36.9? long, 2 Rigid Interconnect: 2.500? OD x 36.9? long, Tool #19 DDS-250 Down hole Shuttle Channel (V,H1, H2) 57, 56, 55: 2.500? OD x 36.9? long, 2 Rigid Interconnect: 2.500? OD x 36.9? long, Tool #18 DDS-250 Down hole Shuttle Channel (V,H1, H2) 54, 53, 52: 2.500? OD x 36.9? long, 2 Rigid Interconnect: 2.500? OD x 36.9? long, Tool #17, 16, 15 DDS-250 Down hole Shuttle Channel (V,H1, H2) 51,50,49,48,47,46,45,44,43: 2.500? OD x 36.9? long, 2 Rigid Interconnect: 2.500? OD x 36.9? long, Tool #14 DDS-250 Down hole Shuttle Channel (V,H1, H2) 42, 41, 40: 2.500? OD x 36.9? long, 2 Rigid Interconnect: 2.500? OD x 36.9? long, - RU Pinnacle Micro seismic tools, ITL hauling KCL water to fill frac tanks. - Continue to PT flow back equipment, Monitoring DFIT. PT all FB equipment to 250 for low, for 5 min w/no leaks. Test same to 8,000 psi for high, for 10 min w/no leaks. RDMO Weatherford test Unit. - No Activity - Conduct PJSM, MIRU

Pinnacle/Halliburton & B&G Crane

Daily Cost: \$0

Cumulative Cost: \$169,464

12/12/2012 Day: 12

Completion

Rigless on 12/12/2012 - Pinnacle Microseismic Tools are in well, POOH to swap out top tool, TIH w/Microseismic tools. - B&G Crane holding Pinnacle sheave while Pinnacle Microseismic Tools are in well. Wait on frac date - 15:00 Pinnacle POOH To fix tool problem between tools 4 and 10 - 17:00 Pinnacle Found the problem at tool geophone number 9. Put in a new geophone at tool 9 Headed back in the hole - Pinnacle left location at 18:00 be back in trhe morning. No activities. - Pinnacle on location with B&G crane POOH with pinnacles tools to change out the top tool.At 10:00 Pinnacle was out of the hole. Changed out top tool and ran back into 1800 feet. Tested tool string to find more problems between tools 4 and 7.

Daily Cost: \$0

Cumulative Cost: \$186,515

12/13/2012 Day: 13

Completion

Rigless on 12/13/2012 - Pinnacle continues to work on their tool string - No activities. - Pinnacle is in position at 9341-8665 feet to monitor the Siesmographic activity from the frac on the Lusty 2-11-3-3WH. - Pinnacle showed up held a Safety meeting went over Jsa's. Started heading to 9341 feet.

Daily Cost: \$0

Cumulative Cost: \$187,577

12/14/2012 Day: 14

Completion

Rigless on 12/14/2012 - Pinnacle is to monitor the siesmographic activity from the frac - Pinnacle is in position at 9341-8665 feet to monitor the Siesmographic activity from the frac on the Lusty 2-11-3-3WH.

Daily Cost: \$0

Cumulative Cost: \$205,613

12/19/2012 Day: 15

Completion

Rigless on 12/19/2012 - RU Baker Hughes frac and J-W Wireline to Perf/Frac stage #1 and #2 - Hold PJSM with personnel on location. Spot in and RU Baker Hughes Frac, J-W Wireline and Tetra flowback to the well. - Held PJSM. RU WL Test to 7,800 Psi. OK. RIH. Wellhead pressure 4,558 Psi. , Set Plug #1@t 9,914' Perforate Stage#2 at (9,878-9878.5'), (9,858-9,859'), (9,843'-9,844').(9,836'-9,837'), (9,791'-9,791.5'),(9,762'-9,763') 60 degrees, 3 spf, POOH, all shots fired WL Turn well over to Baker to Frac Stage 2 - Hydraulic Fracture Deep Wasach stage #2 as follows: Break down 3.8 bpm @ 6,355 psi. Avg rate: 30 bpm, Avg press: 7,125 psi, Max rate: 42 bpm, Max press: 7,805 Psi. FG.0.949, ISIP: 5,064 PSI, 5 MIN: 0 psi, 10 MIN: 0 psi. 15 MIN: 0 psi. Total 20/40 White: 119,941 lbs, Total 15% FE acid 1260 gal. Avg HHP: 5,239 Total load to recover 2,582 Bbls. - Held PJSM with Baker Hughes, J-W Wireline, Tetra, Halliburton and Rockwater on location. Pressured tested the frac lines to a low side 300 psi and held it for 1 minute and tested the high side to 9000 psi. Presure tested the flowback lines to 9000 psi. - Conduct PJSM, RU WL to RIH. Test to 8500 Psi. OK. RIH to Perforate Stage 1 at 10,159'-9'980'. ? guns at 120 degrees, 3 spf, 27 holes. POOH. All shots fired. Hand well over to Baker Hughes frac. - Hydraulic Fracture Deep Wasach stage 1 as follows: Break down 5.2 bpm @ 6,479 psi. Avg rate: 51 bpm, Avg press: 6,686 psi, Max rate: 60 bpm, Max press:

7,594 Psi. FG.0.935, ISIP: 4,860 PSI, 5 MIN: 4,875 psi, 10 MIN: 4,825 psi. 15 MIN: 4,795 psi. Total 20/40 White: 110,089 lbs, Total 15% FE acid 630 gal. Avg HHP: 8,374 Total load to recover 2,775

Daily Cost: \$0

Cumulative Cost: \$232,200

12/20/2012 Day: 16**Completion**

Rigless on 12/20/2012 - Perf/Frac stage #3, Perf/Frac stage #4, Perf/Frac stage #5, RD Baker Hughes and J-W Wireline. - Baker Hughes hauling Frac equipment off location, ND FMC 7-1/16" 10K manual frac stack (hot shot to town using Western WS) NU Knight Oil tools 7-1/16" 5K BOP, stacked as follows FMC 7-1/16" 10K HCR, 7-1/16" 10K-5K x-o 1- 7-1/16" 5k Blind, mud cross w/ double wings, 1- 7-1/16" 5k pipe rams 1- 5K hydril. Torque bolts, prepare to PT. w/ Weatherford test unit. - Held PJSM. RU WL Test to 8900 Psi. OK. RIH. Wellhead pressure 3,500 Psi. , Set Plug Kill plug @ 8,747' and POOH.RD and move off location. - Hydraulic Fracture Deep Wasach stage #5 as follows: Break down 2.9 bpm @ 7,048 psi. Avg rate: 50 bpm, Avg press: 6,757 psi, Max rate: 62 bpm, Max press: 7,524 Psi. FG.0.918, ISIP: 4,563PSI, 5 MIN: 4,258 psi, 10 MIN: 4,218 psi. 15 MIN: 4,188 psi. Total 20/40 White: 159,907 lbs, Total 15% FE acid 1260 gal. Avg HHP: 8,314 Total load to recover 2,721 Bbls. SWI and handed it over to wireline to to set kill plug. Start RD process - Held PJSM. RU WL Test to 7,900 Psi. OK. RIH. Wellhead pressure 4,200 Psi. , Set Plug #4@ 8,895' Perforate Stage#5 at (8,852'-8,857'), (8,872'-8,876'). 120 degrees, 3 spf, POOH, all shots fired WL Turn well over to Baker to Frac Stage #5 - Held PJSM. RU WL Test to 7,900 Psi. OK. RIH. Wellhead pressure 4,076 Psi. , Set Plug #3@ 9,521' Perforate Stage#4 at (9,471-9.473'), (9,441-9,443'), (9,375'-9,377').(9,356'-9,359'). 120 degrees, 3 spf, POOH, all shots fired WL Turn well over to Baker to Frac Stage 4 - Hydraulic Fracture Deep Wasach stage #3 as follows: Break down 13.5 bpm @ 6,960 psi. Avg rate: 47 bpm, Avg press: 6,870 psi, Max rate: 63 bpm, Max press: 7,685 Psi. FG.0.923, ISIP: 4,720PSI, 5 MIN: 4,455 psi, 10 MIN: 4,375 psi. 15 MIN: 4,335 psi. Total 20/40 White: 179,807 lbs, Total 15% FE acid 1260 gal. Avg HHP: 7,931 Total load to recover 3,260 Bbls. - Held PJSM. RU WL Test to 7,800 Psi. OK. RIH. Wellhead pressure 4,648 Psi. , Set Plug #2@ 9,744 ' Perforate Stage#3 at (9,717-9.719'), (9,668-9,669'), (9,630'-9,632').(9,622'-9,624'), (9,562'-9,563'),(9,553'-9,554') 120 degrees, 3 spf, POOH, all shots fired WL Turn well over to Baker to Frac Stage 3 - Hydraulic Fracture Deep Wasach stage #4 as follows: Break down 2.9 bpm @ 7,048 psi. Avg rate: 50 bpm, Avg press: 6,757 psi, Max rate: 62 bpm, Max press: 7,524 Psi. FG.0.918, ISIP: 4,563PSI, 5 MIN: 4,258 psi, 10 MIN: 4,218 psi. 15 MIN: 4,188 psi. Total 20/40 White: 159,907 lbs, Total 15% FE acid 1260 gal. Avg HHP: 8,314 Total load to recover 2,721 Bbls. SWI and handed it over to wireline stage #5. Baker Hughes was down for 1.5 hours bucketing chemicals due to the transfer pumps wouldn't pump the chemicals in this cold weather.

Daily Cost: \$0

Cumulative Cost: \$587,265

12/21/2012 Day: 17**Completion**

Rigless on 12/21/2012 - RU Mountain States work over unit, finish BOP test, PU BHA TIH - Current operations: Still Presure testing the BOP stack which goes as follows-7-1/16" 5k BOP flanges torqued up to API specs, Weatherford test unit dead head to unit test to 5 k 10 min. Test 7-1/16" HCR test from spool up, Door seal failed on 2 3/8" pipe rams. Changed out the door seal, - RU Mountain States Rig To do the drillout. Still trying to test the BOP stack. We Keep blowing the door seals on the stack. Setting one anchor with Benco anchors. Set the frac tanks on one of them. - Ran some hot water thru the BOP stack and started doing a fresh test starting on the Shell test, bottom flange 10k master valve, Blind rams, bottom 2 3/8" pipe rams, top 2 3/8" pipe rams, did 2- 2 1/16" valves on BOP and flowcross to Newfeilds guidelines. Tested the annular bag to 70% of of rating at 3500psi. Placed surge bottle off the

annular valve. Rig is rigged up and placed pipe rack, powerswivel, catwalk and pump and tank. Talling 2 3/8", 4.7#, L-80, EUE 8rd tubing. BOP stack is tarped and rig heater is in place. - Held Pre-Job safety meeting, talked about cold conditions temperatures to be below 0 degrees, Circulating fluids forced heat on well heads. - Mountain Well Service adjusting brake on work over unit, top row of 2-3/8? 4.7# L80 tbg tallied, Tx KCL to mud tank to keep Weatherfords pump circulating while PU tbg. - Current Operation: PU BHA, RIH W/ 3.750? O.D.x 1.00? I.D x 0.35? Hurricane Insert Mill.w/ 2.375? Reg. pin up (1- 2.375? Reg. Box x Pin Float Sub w/ 1R Float 3.250? O.D. x 1.00? I.D. x 0.90? (1- BRS20 Bit Release Sub w/ 1R Float 2.375? Reg. Box down x 2.375? EUE Box up 3.250? O.D. x 1.00? I.D. x 1.77? (1- Joint 2.375 x 32.29? I-80 4.7# EUE Tubing (1- 3.062?? x 1.875? I.D. x 1.28? WX profile Nipple w/ 1.875? Seal bore w/ 2.375? N-80 EUE Coupling. PU of racks TIH filling tubing every 1,000?, Tally tubing (2305 Current Operation : RIH 2.375? 4.7# L--80 tubing w/ BHA #1 @ approx 3126?, Filling tubing and tally second row. 10 Bbls to fill. - Current operations: 7-1/16" 5k BOP flanges torqued up to API specs, Weatherford test unit dead head to unit test to 5 k 10 min. Test 7-1/16" HCR test from spool up,

Daily Cost: \$0

Cumulative Cost: \$628,221

12/22/2012 Day: 18**Completion**

Rigless on 12/22/2012 - Drillout the kill plug, Drillout Frac Plug #1, #2, #3, #4 Cleanout to PBTD. - Done mixing KCL water. Tagged up on the kill plug at 8747' (joint 280). Kicked on the power swivel at started drilling. - Mixing KCL and fresh water to a 7% KCL solution. Four feet off the Kill plug @ 8743'. - 0445 Current Operation : PU 280 Jts. 2-3/8? 4.7# N-80 Tbg w/ BHA #1 Tag up kill Plug @ 8,747? Preparing to PU Power swivel, Weatherford circulating equipment RU ready to pump, Tetra flow back - Current Operation: PU BHA, RIH W/ 3.750? O.D.x 1.00? I.D x 0.35? Hurricane Insert Mill.w/ 2.375? Reg. pin up (1- 2.375? Reg. Box x Pin Float Sub w/ 1R Float 3.250? O.D. x 1.00? I.D. x 0.90? (1- BRS20 Bit Release Sub w/ 1R Float 2.375? Reg. Box down x 2.375? EUE Box up 3.250? O.D. x 1.00? I.D. x 1.77? (1- Joint 2.375 x 32.29? I-80 4.7# EUE Tubing (1- 3.062?? x 1.875? I.D. x 1.28? WX profile Nipple w/ 1.875? Seal bore w/ 2.375? N-80 EUE Coupling. PU of racks TIH filling tubing every 1,000?, Tally tubing (2305 Current Operation : RIH 2.375? 4.7# L--80 tubing w/ BHA #1 @ approx 3126?, Filling tubing and tally second row. 3.87 Bbl/ 1,000' - Current Operation : Finished Circulating 584 Bbls., (7% KCL) . 4,400 Psi @ 3 Bbls/min., Pre-prepare to land 2-3/8? 4,7# N-80 Production string, Cameron on location w/ hanger, TWCV / Production tree, B&G Crane to ND BOP/ NU Production tree, Knight Oil tools ND sections of 5k BOP load out tx. t/ town, Will take 5K annular off 1-11-3-3W and install on the 2-11-3-3 WH, Rustin Mair Torque and Test, Western WS to hot shot BOP to Knight oil tools yard. - 1930 Current Operation : Swivel Back, Drained all fluids, Circulating Weatherfords pump, POOH to 8,802?, (2130 Current Operations : LD 2-3/8? 4.7# N-80 @ 8802? Circulating Surface to Surface 273 Bbls.x 2 3.0 Bbls/Min. @ 4,400 Psi. - Tagged sand at 10,473' (Jt. 335) at 15:05. Washed down to PBTD @ 10,616' (Jt. 340) At 16:30. Started pumping a sweep @ 16:30, PIR-3bpm @ 4500 psi, returns 3.5 bpm 2900 psi. WOB-8K, PU WT-42K, NEU WT-40K, SO WT 28K. - Tagged sand at 9,909' (Jt. 317) at 14:25. Tagged up on #4 Frac plug @ 9,914' (Jt. 318) At 14:35. Tagged up 2 feet higher then actual depth. start drilling @ 14:50, PIR-2.8bpm @ 4300 psi, returns 3.5 bpm 3150psi. WOB-8K, PU WT-38K, NEU WT-36K, SO WT 34K. 15:00 thru Frac Plug #4 plug 10 mins. pump 10 bbl sweep set swivel back. Continue RIH to PBTD @ 10,597.58 - Tagged sand at 9,716' (Jt. 311) at 13:10. Tagged up on #3 Frac plug @ 9,753' (Jt. 312) At 13:25. Tagged up 9 feet lower then actual depth. start drilling @ 13:25, PIR-2.8bpm @ 4200 psi, returns 3.5 bpm 3000 psi. WOB-8K, PU WT-34K, NEU WT-32K, SO WT 30K. 13:50 thru Frac Plug #3 plug 20 mins. pump 10 bbl sweep set swivel back. Continue RIH to frac plug #4 @ 9,914'. - Tagged sand at 9,434' (Jt. 302) Tagged up on #2 Frac plug @ 9,521' (Jt. 305) At 12:00. Tagged at actual depth. start drilling @ 12:02, PIR-3bpm @ 3100 psi, returns 3.5 bpm 2000 psi. WOB-8K, PU WT-34K, NEU WT-32K, SO WT 30K. 12:22 thru Frac Plug #2 plug 20 mins. pump 10 bbl sweep set swivel back. Continue RIH to frac plug #3 @ 9,744'. - Tagged sand at 8865' (Jt. 283) Tagged up on

#1 Frac plug @ 8,895' (Jt. 284) At 09:35. Tagged at actual depth. start drilling,PIR-3bpm @ 3100 psi,returns 3.5 bpm 2000 psi.WOB-8K,PU WT-34K,NEU WT-32K,SO WT 30K. 09:58 thru Frac Plug #1 plug 18 mins. pump 10 bbl sweep set swivel back.Continue RIH to frac plug #2 @ 9,521'. - Continue RIH with tubing down to Kill plug @ 8,747' Tagged up on Jt. 280. Tagged at actual depth. start drilling,PIR-2.9 bpm @ 3800 psi,returns 3.5 bpm 2500 psi.WOB-8K,PU WT-34K,NEU WT-32K,SO WT 30K. 08:40 thru kill plug 25 mins. pump 10 bbl sweep set swivel back.Continue RIH to frac plug #1 @ 8,895'.

Daily Cost: \$0

Cumulative Cost: \$676,622

12/23/2012 Day: 19**Completion**

Rigless on 12/23/2012 - ND BOP, HCR, NU Production tree rig workover unit. De-Mob - Current Operation :Knight oil tools 7-1/16? 5k BOP ND loaded out w/ closing unit on Western w/s hotshot, FMC 7-1/16? 10k HCR w/ closing unit loaded out on Western w/s hotshot both going to Vernal Utah. Cameron NU 10K Production tree. Hauling pit water to disposal, Mountain w/s will be rigging down as soon as tree is NU void tested. Weatherford circulating unit RD off Lusty 1-11-3-3W, drained laying hardline to Lusty 2-11-3-3 WH, Tetra flow testers RD Lusty 1-11-3-3W Drained, moved flowback line to Lusty 2-11-3-3WH RU to wellhead but not connected. - 0430 Current Operations : PT void 10k production tree to 7-1/16? raised neck hanger 9,500 Psi high 10 min. 250 Psi low 5 min. test good, Laying derrick over then presume w/ PT body of 10k production tree. After a visual inspection of annular bag worn, missing chunks or rubber, steel finger bent possibly from collars on 2-3/8? EUE collars, Knight oil tools changing out annular have one on the floor in Vernal in transit - Tested Production tree to 9500K. Tested good. Move the rig to the Lusty 2-11-3-3WH. - Here whats in the well from top to bottom- Tbg.extened neck Hanger ID. 2 3/8" 8 rd. EUE., 280jts. (8771.84), 2 3/8" EUE 8rnd "WX" Profile Nipple with 1.875" Seal Bore with 2 3/8" N-80 Coupling. 1- 2 3/8" joint (30.98)., BRS20 Bit Release Sub with 1R Float 2 3/8" Reg. Box Down X 2 3/8" EUE Box Up (Note: The Top Sub of the BRS 20 has a 3 1/16" O.D. Fishing Neck .48' long at t., 2 3/8" Reg. Box X Pin Float Sub with 1R Float. & 3 3/4" Hurricane Insert Mill with 2 3/8" Reg Pin up. When receive orders from Newfeild to drop ball and pump off bit. Moved rig off the well. Cameron pulled back pressure valve. - 0045 Current Operation : Tubing hanger landing joint marked, measured, hanger landed in bowl, set screws and packing glands tighten, pressures bleed off, closing unit pressure bleed off, Moving skater, pipe racks, RU B&G Crane, ND BOP and HCR. Current temperatures -12 degrees.

Daily Cost: \$0

Cumulative Cost: \$872,400

12/27/2012 Day: 23**Completion**

Rigless on 12/27/2012 - No Work Completed - No Work Done - No Work Done - No Work Done - No Work Done - No Work Done - No Work Done - No Work Done - No Work Done - No Work Done - No Work Done - No Work Completed. Well shut in. - No Work Completed. Well shut in. - No Work Completed. Well shut in. - No Work Completed. Well shut in. - No Work Done

Daily Cost: \$0

Cumulative Cost: \$902,972

12/28/2012 Day: 24**Completion**

Rigless on 12/28/2012 - Well shit in no activity - No activity. Well shut in.

Daily Cost: \$0

Cumulative Cost: \$1,076,226

12/29/2012 Day: 25

Completion

Rigless on 12/29/2012 - No activity - Well shut in no activity Price up date

Daily Cost: \$0

Cumulative Cost: \$1,089,278

1/1/2013 Day: 26

Completion

Rigless on 1/1/2013 - Pump down tbg and pump off bit, Turn well over to production Dept - . Turn well over to production dept - RU Weatherford to well head pressure puming and line 5,000 psi, Good test. Hole well head pressure @ 2800 psi. Start pumping @ 2.5 bMP @ 3500 psi Pressure increase to 4000 psi and drop back to 3300 psi, pump 30 bbls BFW and 30 bbl of BBW shut down ISIP @ 3400 psi 5 min 3100 psi. Shut well in. RDMO Weatherford pumping ser. - Well shut in no activity

Daily Cost: \$0

Cumulative Cost: \$1,091,952

1/5/2013 Day: 27

Completion

Rigless on 1/5/2013 - Capture Costs in DCR - Capture Costs in DCR

Daily Cost: \$0

Cumulative Cost: \$1,095,345

1/26/2013 Day: 29

Completion

Rigless on 1/26/2013 - Run PLS log w/ Halliburton. Return well to production. Job complete. - 14:00 ? POOH w/ logging tools. 13:30 ? Station stops @ top of stages: Stg# Depth Temp PSI Spinner Dens GHT Rate 1 9960? 223 3283 1.09 0.96 20142 2 9750? 220 3193 0.53 0.97 20058 3 9530? 193 3101 1.91 0.92 19639 4 9340? 215 3025 2.83 0.83 19285 5 8830? 211 2838 2.41 0.85 18955 - 16:30 ? Job complete. All personnel off location. 15:30 ? OOH. SI crown valve. Bleed down pressure. RD & loadout logging equipment. - 08:30 ? Start logging @ 8820? at top perf. Log down to 10,190? & up to 8820? @ 30?, 60 & 120? per min. 07:00 - Open well & RIH w/ Halliburton logging tools to 8845?. Sales Rate 225 scfm. SICP ? 1050 psi. FTP ? 210 psi. - 06:45 - Spot & RU Four Star pressure test truck. Pressure test lubricator to 4300 psi. Good test. Bleed pressure down to 300 psi. 06:15 - FTP - 250 psi. Spot & RU Halliburton logging equipment. 06:00 - JSA w/ Halliburton. Discuss: PPE, slips, trips, falls, pinch points, muster points, smoking policy, high pressure, mentors & days operations.

Daily Cost: \$0

Cumulative Cost: \$1,135,261

2/27/2013 Day: 31

Completion

Rigless on 2/27/2013 - Capture Costs in DCR - Capture Costs in DCR from a delayed ticket from FMC. Vendor was contacted to discuss delivery of tickets to location and getting them in a timely fashion. Coist adjustments from Knight and Cleaning of R4R tanks costs. Capture delayed BOP repairs from Knight. Delay due to revisions made per NFX request. 7/9/13

Daily Cost: \$0

Cumulative Cost: \$1,191,242

3/13/2013 Day: 1**Conversion**

Nabors #1420 on 3/13/2013 - MIRU WOR.ND WH. NU BOP. Test BOP. - - Install TWCV. ND WH. NU BOP. Spot in Weatherford test pump. Perform dead head test on pump, found check valve leaking. Replace check valve and retest, OK. Test outside wing valve to 250 psi, found small leak in stem packing. BO pressure and function valve. Test outside wing valve to 250 psi for 5 minutes, OK. BO pressure. Pressure to 5000 psi for 10 minutes, OK. BO pressure. Test inside wing valve to 250 psi for 5 minutes, OK. BO pressure. Pressure to 5000 psi for 10 minutes, OK. BO pressure. Test blind rams to 250 psi for 5 minutes, battery dead on chart recorder. Replaced battery, recorder still would not work. Replaced battery with a good battery. Test blind rams to 250 psi for 5 minutes, OK. BO pressure. Pressure to 5000 psi for 10 minutes, OK. BO pressure. PU tbg pup and TIW valve. Test pipe rams and TIW to 250 psi for 5 minutes, OK. BO pressure. Pressure to 5000 psi for 10 minutes, OK. BO pressure. Test annular preventer to 3500 psi for 10 minutes, OK. Remove pup and TIW. Secure well, location, and equipment. SDFN. - - JSA and safety meeting. SITP 1000 psi. FCP 100 psi. MIRU Nabors Rig #1420. Spot in HO trk.BO tbg. Pump 70 bbl hot water down tbg. RDMO HO trk. - Install TWCV. ND WH. NU BOP. Spot in Weatherford test pump. Perform dead head test on pump, found check valve leaking. Replace check valve and retest, OK. Test outside wing valve to 250 psi, found small leak in stem packing. BO pressure and function valve. Test outside wing valve to 250 psi for 5 minutes, OK. BO pressure. Pressure to 5000 psi for 10 minutes, OK. BO pressure. Test inside wing valve to 250 psi for 5 minutes, OK. BO pressure. Pressure to 5000 psi for 10 minutes, OK. BO pressure. Test blind rams to 250 psi for 5 minutes, battery dead on chart recorder. Replaced battery, recorder still would not work. Replaced battery with a good battery. Test blind rams to 250 psi for 5 minutes, OK. BO pressure. Pressure to 5000 psi for 10 minutes, OK. BO pressure. PU tbg pup and TIW valve. Test pipe rams and TIW to 250 psi for 5 minutes, OK. BO pressure. Pressure to 5000 psi for 10 minutes, OK. BO pressure. Test annular preventer to 3500 psi for 10 minutes, OK. Remove pup and TIW. Secure well, location, and equipment. SDFN. - Install TWCV. ND WH. NU BOP. Spot in Weatherford test pump. Perform dead head test on pump, found check valve leaking. Replace check valve and retest, OK. Test outside wing valve to 250 psi, found small leak in stem packing. BO pressure and function valve. Test outside wing valve to 250 psi for 5 minutes, OK. BO pressure. Pressure to 5000 psi for 10 minutes, OK. BO pressure. Test inside wing valve to 250 psi for 5 minutes, OK. BO pressure. Pressure to 5000 psi for 10 minutes, OK. BO pressure. Test blind rams to 250 psi for 5 minutes, battery dead on chart recorder. Replaced battery, recorder still would not work. Replaced battery with a good battery. Test blind rams to 250 psi for 5 minutes, OK. BO pressure. Pressure to 5000 psi for 10 minutes, OK. BO pressure. PU tbg pup and TIW valve. Test pipe rams and TIW to 250 psi for 5 minutes, OK. BO pressure. Pressure to 5000 psi for 10 minutes, OK. BO pressure. Test annular preventer to 3500 psi for 10 minutes, OK. Remove pup and TIW. Secure well, location, and equipment. SDFN. - JSA and safety meeting. SITP 1000 psi. FCP 100 psi. MIRU Nabors Rig #1420. Spot in HO trk.BO tbg. Pump 70 bbl hot water down tbg. RDMO HO trk. - JSA and safety meeting. SITP 1000 psi. FCP 100 psi. MIRU Nabors Rig #1420. Spot in HO trk.BO tbg. Pump 70 bbl hot water down tbg. RDMO HO trk. -

Daily Cost: \$0**Cumulative Cost:** \$12,205**3/14/2013 Day: 2****Conversion**

Nabors #1420 on 3/14/2013 - Kill well. TOH. Run prod tbg. - JSA and safety meeting. FCP 25 psi. Spot in Cameron. Lubricate TWCV out of tbg hanger. SITP 720 psi. BO pressure. Roll hole with 310 bbl produced water. Tally tbg OH 100 stands. Pump 110 bbl brine down csg to kill well. Finish TOOH. LD XN nipple, 1 jt tbg, and bit release sub. PU pump assembly and TIH with 122 jts to 3,910?. Secure well, location, and equipment. SDFN. - JSA and safety meeting. FCP 25 psi. Spot in Cameron. Lubricate TWCV out of tbg hanger. SITP 720 psi. BO pressure. Roll hole with 310 bbl produced water. Tally tbg OH 100 stands. Pump 110 bbl brine down csg

to kill well. Finish TOOH. LD XN nipple, 1 jt tbg, and bit release sub. PU pump assembly and TIH with 122 jts to 3,910?. Secure well, location, and equipment. SDFN. - JSA and safety meeting. FCP 25 psi. Spot in Cameron. Lubricate TWCV out of tbg hanger. SITP 720 psi. BO pressure. Roll hole with 310 bbl produced water. Tally tbg OH 100 stands. Pump 110 bbl brine down csg to kill well. Finish TOOH. LD XN nipple, 1 jt tbg, and bit release sub. PU pump assembly and TIH with 122 jts to 3,910?. Secure well, location, and equipment. SDFN.

Daily Cost: \$0

Cumulative Cost: \$27,686

3/15/2013 Day: 3**Conversion**

Nabors #1420 on 3/15/2013 - Finish running prod tbg. Kill well. Set TAC. ND BOP. NUWH. Clean up equipment. - Spot in HO trk. Clean oil and paraffin off equipment. Break out and rack csg lines. Change rig equipment from tbg to rods. Secure well, location, and equipment. SDFN. - JSA and safety meeting. SICP 120 psi. SICP 570 psi. BO pressure on tbg. BO csg, slight flow. TIH with 98 jts. PU 48 jts tbg. Prod tbg as follows: 326 jts 2-3/8? 4.7# EUE 8rd L-80 tbg, 2-3/8? x 4-1/2? TAC, 1 jt 2-3/8? 4.7# EUE 8rd L-80 tbg , SN with 1-25/32? ID, 2-3/8? Cavins desander 19.25? L, 2 jts 2-3/8? 4.7# EUE 8rd L-80 tbg , Cavins dump valve. TAC @ 10,208.46?. SN @ 10,243.77?. Desander @ 10,249.03?. EOT @ 10330.18?. Ttl 328 jts in hole. Pump 50 bbl brine down csg and 10 bbl brine down tbg to kill well. Well started flowing up tbg while removing Washington rubber. Shut in csg. Pump 25 bbl brine down tbg, on vac. Set TAC with 8? pup. Land tbg with TAC in compression. ND BOP. Slight flow on csg. Pump 10 bbl brine down tbg. Pump 60 bbl down csg. Remove 8? pup and land tbg with 24K tension. NU WH. - JSA and safety meeting. SICP 120 psi. SICP 570 psi. BO pressure on tbg. BO csg, slight flow. TIH with 98 jts. PU 48 jts tbg. Prod tbg as follows: 326 jts 2-3/8? 4.7# EUE 8rd L-80 tbg, 2-3/8? x 4-1/2? TAC, 1 jt 2-3/8? 4.7# EUE 8rd L-80 tbg , SN with 1-25/32? ID, 2-3/8? Cavins desander 19.25? L, 2 jts 2-3/8? 4.7# EUE 8rd L-80 tbg , Cavins dump valve. TAC @ 10,208.46?. SN @ 10,243.77?. Desander @ 10,249.03?. EOT @ 10330.18?. Ttl 328 jts in hole. Pump 50 bbl brine down csg and 10 bbl brine down tbg to kill well. Well started flowing up tbg while removing Washington rubber. Shut in csg. Pump 25 bbl brine down tbg, on vac. Set TAC with 8? pup. Land tbg with TAC in compression. ND BOP. Slight flow on csg. Pump 10 bbl brine down tbg. Pump 60 bbl down csg. Remove 8? pup and land tbg with 24K tension. NU WH. - JSA and safety meeting. SICP 120 psi. SICP 570 psi. BO pressure on tbg. BO csg, slight flow. TIH with 98 jts. PU 48 jts tbg. Prod tbg as follows: 326 jts 2-3/8? 4.7# EUE 8rd L-80 tbg, 2-3/8? x 4-1/2? TAC, 1 jt 2-3/8? 4.7# EUE 8rd L-80 tbg , SN with 1-25/32? ID, 2-3/8? Cavins desander 19.25? L, 2 jts 2-3/8? 4.7# EUE 8rd L-80 tbg , Cavins dump valve. TAC @ 10,208.46?. SN @ 10,243.77?. Desander @ 10,249.03?. EOT @ 10330.18?. Ttl 328 jts in hole. Pump 50 bbl brine down csg and 10 bbl brine down tbg to kill well. Well started flowing up tbg while removing Washington rubber. Shut in csg. Pump 25 bbl brine down tbg, on vac. Set TAC with 8? pup. Land tbg with TAC in compression. ND BOP. Slight flow on csg. Pump 10 bbl brine down tbg. Pump 60 bbl down csg. Remove 8? pup and land tbg with 24K tension. NU WH. - Spot in HO trk. Clean oil and paraffin off equipment. Break out and rack csg lines. Change rig equipment from tbg to rods. Secure well, location, and equipment. SDFN. - Spot in HO trk. Clean oil and paraffin off equipment. Break out and rack csg lines. Change rig equipment from tbg to rods. Secure well, location, and equipment. SDFN.

Daily Cost: \$0

Cumulative Cost: \$38,150

3/16/2013 Day: 4**Conversion**

Nabors #1420 on 3/16/2013 - PU pump and rods. - JSA and safety meeting. Hot water well with 35 bbl produced water. At that point HO truck (Preferred Hot Oil Serv) loaded with 40 bbl brine to kill tbg. He had 15 bbl prod water on trk, diluting brine. Pumped diluted brine down tbg to kill well. Called for 50 bbl more brine to kill well. HO truck was also 2 hrs late. PU new

2? x 1.5? x 36 RHBC pump (#NF646J), 16-7/8? Tenaris MMS 4per rods, 160-3/4? Tenaris MMS slick rods, 94-3/4? Tenaris 4per rods, 136-7/8? Tenaris 4per rods, 1-7/8? x 2? pony, and 1-1/2? X 40? polished rod with turned down pins. Space out rods with pump 3? off bottom. Clamp off rods. Load tbg with 6 bbl produced water. Long stroke pump, good pump action. RDMO WOR. Slide RotoFlex unit forward on skid. - JSA and safety meeting. Hot water well with 35 bbl produced water. At that point HO truck (Preferred Hot Oil Serv) loaded with 40 bbl brine to kill tbg. He had 15 bbl prod water on trk, diluting brine. Pumped diluted brine down tbg to kill well. Called for 50 bbl more brine to kill well. HO truck was also 2 hrs late. PU new 2? x 1.5? x 36 RHBC pump (#NF646J), 16-7/8? Tenaris MMS 4per rods, 160-3/4? Tenaris MMS slick rods, 94-3/4? Tenaris 4per rods, 136-7/8? Tenaris 4per rods, 1-7/8? x 2? pony, and 1-1/2? X 40? polished rod with turned down pins. Space out rods with pump 3? off bottom. Clamp off rods. Load tbg with 6 bbl produced water. Long stroke pump, good pump action. RDMO WOR. Slide RotoFlex unit forward on skid. - JSA and safety meeting. Hot water well with 35 bbl produced water. At that point HO truck (Preferred Hot Oil Serv) loaded with 40 bbl brine to kill tbg. He had 15 bbl prod water on trk, diluting brine. Pumped diluted brine down tbg to kill well. Called for 50 bbl more brine to kill well. HO truck was also 2 hrs late. PU new 2? x 1.5? x 36 RHBC pump (#NF646J), 16-7/8? Tenaris MMS 4per rods, 160-3/4? Tenaris MMS slick rods, 94-3/4? Tenaris 4per rods, 136-7/8? Tenaris 4per rods, 1-7/8? x 2? pony, and 1-1/2? X 40? polished rod with turned down pins. Space out rods with pump 3? off bottom. Clamp off rods. Load tbg with 6 bbl produced water. Long stroke pump, good pump action. RDMO WOR. Slide RotoFlex unit forward on skid.

Daily Cost: \$0

Cumulative Cost: \$301,145

Pertinent Files: Go to File List